

BAY COUNTY REMONUMENTATION 1999  
LAND CORNER RECORDATION CERTIFICATE  
Filing Requirement of Act 74, Mich. P.A. 1970

SECTION

For corners in

MERRITT TOWNSHIP

Located in:

Corner Code #

BAY  
(County)

1. Public Land Survey T 13N R 6E E-12  
T R  
2. Property Controlling S T R  
3. Miscellaneous S T R  
Property in Sec. S T R

Barbara Grace Kistner  
REGISTER OF DEEDS  
BAY COUNTY, MICHIGAN

1999 DEC 29 P 12:53

RECORDED

Register of Deeds Stamp & File Number

4. Lot No. \_\_\_\_\_, Recorded Plat \_\_\_\_\_  
5. Private Claims \_\_\_\_\_

I, BRIAN D FERGUSON, in a field survey on MAY, 19 99 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

A	B	C	D	E	F	G	H	I	J	K	L	M
1												
2	6		5		4		3		2			
3												
4	7		8		9		10		11		12	
5												
6	18		17		16		15		14		13	
7												
8	19		20		21		22		23		24	
9												
10	30		29		28		27		26		25	
11												
12	31		32		33		34		35		36	
13												

- A. Description of original monument and accessories and/or subsequent restoration:

WOOD POST SET BY J. WAMPLER, DS, IN 1821. NO EVIDENCE OF ORIGINAL CORNER REMAINS.  
LCRC BY QUIST, L002 P516, IN 1979  
COS BY EDMANDS ENG, L885 P857; L888 P231;  
COS BY MCGINNIS, L759 P33  
COS BY PREVOST, L1121 P09  
COS BY BURGIN, L1307 P633

- B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

FOUND 3/4" PIPE PER LCRC AND COS'S  
MEASURED 2632.98' TO C-13 (REC 2633.11' L1307 P633)  
MEASURED 2629.89' TO E-11 (REC 2630.32' L885 P857)

ACCEPTED AS THE BEST AVAILABLE EVIDENCE OF THE LOCATION OF THE ORIGINAL CORNER

- C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

SET 5/8" RE-BAR W / BAY COUNTY REMON. BRASS CAP & NO. 26454 IN MONUMENT BOX  
S85E 137.50' N LEG POST OF SIGN  
S05E 19.90' BTM CTR STEEL "T" POST (REC 19.80' L11307 P633 & LCRC)  
EAST 27.2' ± WEST EDGE POLE BARN EXTENDED S'LY (REC 27.2' ± L1121 P09)  
N45W 21.21' 1/2" REBAR W/CAP  
N45E 21.21' 1/2" REBAR W/CAP

Signed by


Brian D Ferguson

Date

December 15, 1999

Surveyor's Michigan License No.

26454



APPROVED LAND CORNER  
P.A. 345 OF 1990 - Bay County  
Date 7.08.99  
MM  
Michael MacDonald P.S.  
Land Surveyor

FORM APPROVED BY MICHIGAN STATE BOARD OF PROFESSIONAL SURVEYORS, JAN. 28, 1971  
REVISED MAY 14, 1975  
REVISED JAN., 1983  
REVISED OCT., 1995

004 337