

RECEIVED
BENZIE COUNTY
REGISTER OF DEEDS

2017 OCT 16 AM 9 56

STATE OF MICHIGAN
BENZIE COUNTY
RECORDED
10/16/2017 10:05:06AM
REC FEE: \$30.00
PAGE 1 OF 2
64907

AMY J BISSELL
REGISTER OF DEEDS

Land Corner Recordation Certificate
Authority: 1970 PA 74, MCL 54.205

Surveyor's Name: Joshua R. Davidson Field Survey Date: November 7, 2016
For corner(s) in: Benzie County

Original Public Land Survey Corner			Corner Code
S	T	R	
S	T	R	
S	T	R	
S	T	R	

Property Controlling Corner			Corner Code
S	34	T 27N R 13W	H12
S		T	R
S		T	R
S		T	R

Property Corner			Corner Code
S		T	R
S		T	R
S		T	R
S		T	R

Protracted Public Land Survey Corner			Corner Code
S		T	R
S		T	R
S		T	R
S		T	R

1	A	B	C	D	E	F	G	H	I	J	K	L	M	1
2		6		5		4		3		2		1		2
3														3
4		7		8		9		10		11		12		4
5														5
6		18		17		16		15		14		13		6
7														7
8		19		20		21		22		23		24		8
9														9
10		30		29		28		27		26		25		10
11														11
12		31		32		33		34		35		36		12
13	A	B	C	D	E	F	G	H	I	J	K	L	M	13

Part A: Corner History

H12 – Center ¼ corner section 34, T27N, R13W

- 1966 – Survey of section 34 – prepared by Norton-Gourdie-Miller-Batzer, Inc.
– old established center post. Old well point found. Center of section 34 by subdivision shown 39.10' east of well point.
- 1976 – DNR working drawing & survey notes project #76-19 – C. Roser, PS # 12028 – found 1¼" well point, North 40.10' to found 1" old pipe.

Part B: Surveyor's Report on Perpetuation, Restoration, Reestablishment, or Monumentation of Corner

H12 – Center ¼ corner section 34, T27N, R13W

Set a 2" aluminum cap on 5/8" X 34" rebar at intersection of ¼ lines using the remon postion of G12. Found ½" rebar in well point N78°W 37.06', and found a 1" pipe N34°W 57.42'.


Part C: Field Evidence of Perpetuation or Monumentation of Corner

H12 – Center ¼ corner section 34, T27N, R13W

a stamped 2" aluminum cap on 5/8" x 34" rebar

N63°E 28.08' to set nail & tag in SE. side 14" tw. S. Maple
S28°E 37.27' to set nail & tag in SW. side 5" S. Maple
N60°W 18.43' to set nail & tag in NE. side 21" Oak
N78°W 37.06' to found ½" rebar in well point
N34°W 57.42' to found 1" pipe

Set blue post with location tag 1' South



Certifying Surveyor's Name

October 10, 2017

Date

Professional Surveyor's License No.: 46659

Prepared By: Joshua R. Davidson
Department of Natural Resources
8015 Mackinaw Trail
Cadillac, MI 49601

