

SURVEY &  
REMONUMENTATION

MAR 13 1998

SECTION

BRANCH COUNTY REMONUMENTATION CORNER  
LAND CORNER RECORDATION CERTIFICATE  
Filing Requirement of Act 74, Mich. P.A. 1970

STATE OF MICHIGAN  
Branch County  
Recorded

For corners in

BRANCH \_\_\_\_\_ Located In: \_\_\_\_\_ Corner Code # \_\_\_\_\_  
(County)  
GILEAD TWP.  
1. Public Land Survey T 8 S R 7 W L-7  
T \_\_\_\_\_ R \_\_\_\_\_  
T \_\_\_\_\_ R \_\_\_\_\_  
T \_\_\_\_\_ R \_\_\_\_\_  
2. Property Controlling S \_\_\_\_\_ T \_\_\_\_\_ R \_\_\_\_\_  
in Section S \_\_\_\_\_ T \_\_\_\_\_ R \_\_\_\_\_  
3. Miscellaneous S \_\_\_\_\_ T \_\_\_\_\_ R \_\_\_\_\_  
Property in Sec. S \_\_\_\_\_ T \_\_\_\_\_ R \_\_\_\_\_

10-22-1997 09:55:32

Linda Lee Morrison-Mathews  
REGISTER OF DEEDS

Liber 00003 Page 0155

Register of Deeds Stamp & File Number

4. Lot No. \_\_\_\_\_, Recorded Plat \_\_\_\_\_  
5. Private Claims \_\_\_\_\_

I, EDWARD W. REED, in a field survey on APRIL 29, 1997 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and for that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:  
QUARTER CORNER COMMON TO SECTIONS 13 & 24

1828: R. CLARK Jr, DEPT. SURVEYOR - SET CORNER  
OLD NOTES: INDICATE IRON IN BROKEN STONES  
1965: PLAT OF "OAK HAVEN NO. 2" TIED TO CORNER  
1973: E.R. REED, CO. SURVEYOR, FOUND IRON SHAFT WITH COLLAR SURROUNDED BY BROKEN STONES  
RECORDED IN LCRC # 0070

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

FOUND IRON SHAFT WITH COLLAR SURROUNDED BY BROKEN STONES WITH FLAGGING  
SET 1/2" X 18" REBAR IRON WITH REMON CAP IN CI-MONUMENT BOX

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:


IN C/L OF EAST-WEST GRAVEL ROAD  
IN LINE WITH FENCES RUNNING NORTH AND SOUTH  
RR-RAIL ANCHOR POST, SOUTH 25.5'  
TEL. PED N69W 85.7' TO FACE  
18" WALNUT, N53W 45.9' TO CENTER

AND IS ACCEPTED AS A CAREFUL AND FAITHFUL PERPETUATION OF THE POSITION OF THE ORIGINAL CORNER

Signed by Edward W. Reed  
EDWARD W. REED

Date APRIL 29, 1997

Surveyor's Michigan License No. 33985



ACCEPTED BY THE BRANCH COUNTY  
SURVEY PEER GROUP AS THE OFFICIAL  
CORNER UNDER MICHIGAN PUBLIC ACT 345  
OF 1990 AT A MEETING HELD ON  
9-18-97

E.R. Reed, P.S. Co. Rep.  
E.R. REED