

SURVEY &  
REMONUMENTATION

APR 26 1995

COMMISSION

LAND CORNER RECORDATION CERTIFICATE

Filing Requirement of Act 74, Mich. P.A. 1970  
CASS COUNTY REMONUMENTATION

STATE OF MICHIGAN  
CASS COUNTY  
RECEIVED FOR RECORD

1994 NOV 8 PM 2 52

For corners in

CASS

(County)

Located In:

Corner Code ##

1. Public Land Survey

T R

T 7 R 14

Meander corner

N. line, Sect. 6

T R

T R

2. Property Controlling  
in Section

S T R

S T R

3. Miscellaneous  
Property in Sec.

S T R

S T R

4. Lot No. , Recorded Plat

5. Private Claims

Ann L. Kesler  
CLERK/REGISTER

BOOK 2 PAGE 351

Register of Deeds Stamp & File Number

Ratified by Peer Group  
In Accordance With P.A. 345  
Chairman

I, Dale L. Kesler, in a field survey on October 6, 1994

do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

**NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.**

A. Description of original monument and accessories and/or subsequent restoration:

1827 - William Brookfield used 10" Beech tree for meander post; 1892 - F.E. Smith found meander corner tree 2.09 chains west of the south quarter corner of Section 31, T. 6 S., R. 14 W.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

Meander corner was not found. Set corner 137.94' (2.09 chains) West of the south quarter corner of Section 31, T.6 S., R.14 W., and used adjacent property corners north and south to reestablish the meander corner.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:


Set 36" concrete monument w/aluminum cap and is accepted as a careful and faithful reestablishment of the position of the original corner.

SW corner of Pool House N. 22° 26' W. 9.70'

SW corner of Square light pole S. 69° 21' E. 2.31'

Found chiseled "X" in concrete sea wall S. 67° 29' W. 6.22'

Set PK nail w/washer in 26" Maple tree S. 65° 43' E. 17.30'



Signed by

Dale L. Kesler

Date

November 8, 1994

Surveyor's Michigan License No.

No. 38117