

LAND CORNER RECORDATION CERTIFICATE  
Filing Requirement of Act 74, Mich. P.A. 1970  
CASS COUNTY REMONUMENTATION

For corners in  
CASS  
(County)

Located In:

Corner Code #

1. Public Land Survey  
S 1/4 Sec. 32

T 7S R 15W

D-13

2. Property Controlling  
In Section  
3. Miscellaneous  
Property In Sec.

S      T      R       
S      T      R       
S      T      R       
S      T      R     

STATE OF MICHIGAN  
COUNTY OF CASS  
Recorded

11-29-1999 13:47:11

Ann L. Simmons  
REGISTER OF DEEDS

Register of Deeds Stamp & File Number

11/29/99  
Ratified by Peer Group  
in Accordance With P.A. 345  
Chairman Dale C. Kesler

4. Lot No.           , Recorded Plat             
5. Private Claims           

I, DALE L. KESLER, in a field survey on OCTOBER 26, 1999 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and /or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

1827 William Brookfield. Measured West 40 chains 1/4 Section Corner in pond measured West 80 chains.  
April 26, 1871 Bradt, County Surveyor. South 1/4 Section Corner lost - established 1/2 way on line.

	A	B	C	D	E	F	G	H	I	J	K	L	M
1													
2		6		5		4		3		2		1	
3													
4		7		8		9		10		11		12	
5													
6		18		17		16		15		14		13	
7													
8		19		20		21		22		23		24	
9													
10		30		29		28		27		26		25	
11													
12		31		32		33		34		35		36	
13													

Liber 00003 Page 0229


B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

Did not find corner. Re-established corner midway and on line between the SW corner and SE corner of Section 32, T7S, R15W.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

Set 3/4" x 6" galvanized pipe with aluminum cap in a 6" PVC pipe in concrete and is accepted as a careful and faithful re-establishment of the position of the original corner.

PK Nail in 5" W. Cherry S 45 deg. W 20.37  
PK Nail in 4" W. Cherry S 40 deg. W 12.09  
PK Nail in 8" W. Cherry S 15 deg. W 16.79  
Corner at South Edge Water of Pleasant Lake Drain



Signed by Dale C. Kesler  
Surveyor's Michigan License No. 38117

Date 11/23/99

FORM APPROVED BY MICHIGAN STATE BOARD OF PROFESSIONAL SURVEYORS, JAN. 28, 1971  
REVISED MAY 14, 1975  
REVISED JAN., 1983  
REVISED OCT., 1995

RECEIVED &  
RECORDED

FEB 24 2000

SECTION