

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970 as Amended

For corners in

Chippewa	Located In:	Corner Code #
(County)		
1. Public Land Survey	T 42N R 2E	F3
	T R	
	T R	
2. Property Controlling in Section	S T R	
	S T R	
	S T R	
3. Miscellaneous Property in Sec.	S T R	
	S T R	
4. Lot No. , Recorded Plat		
5. Private Claims		

Register of Deeds Stamp & File Number

	A	B	C	D	E	F	G	H	I	J	K	L	M
1													
2	6		5			4		3		2		1	
3													
4	7		8			9		10		11		12	
5													
6	18		17			16		15		14		13	
7													
8	19		20			21		22		23		24	
9													
10	30		29			28		27		26		25	
11													
12	31		32			33		34		35		36	
13													

I, Stephan J. Szyszkoski, in a field survey on 08/18/2009 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and /or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

(F3) Quarter corner common to Sections 4 and 9. 1845 - Established by John Mullett Deputy Surveyor. Set post midway and on the Section line between Section corners 40.06 chains east and west. Tamarack 8" S47E 6 links, Cedar 6" N12E 28 links. 1969 - Reestablished by Billy D. Buckler RLS midway between Section corners and in center of E-W road. Set 1"x36" I.pipe buried in center of road. 8" Tamarack N24E 29.0', 10" Cedar N20W 33.7'. 1987 - Remonumented at the 1969 position by Gerald A. Myers RLS who recovered the 1969 witness tress but not the 1969 iron pipe monument. Set 1/2"x22" rebar with cap 6" below road surface. Mr. Myers set a nail in: 6" Cedar S10W 30.40', 10" triple Cedar N20W 32.27', 10" Tamarack N35E 30.39'. Rec. Liber 7 of LCRC, Page 088.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

(F3) Found the 1/2" rebar noted in the 1987 record disturbed, bent over at the road surface. The lower part of the monument was found plumb and in position at record bearing and distance from the 1987 accessories. The Cedar NBTs are in good condition, the Tamarack NBT is dead. Removed the 1/2" rebar and at the position for the corner, drove a 5/8"x18" capped rebar in its place, to 6" below the gravel road surface.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

(F3) Set 5/8"x18" rebar with plastic MDNR cap 6" below surface. Fd. nail in the side of: 11" triple Cedar N12W 32.26' old blazes 7" Cedar S19W 30.41' mrkd "1/4S NBT" Found 1/2" rebar w/cap #22428 N10E 33.1' Set measuring nail with MDNR tag in the side of: 7" Cedar S14E 29.05' mrkd "1/4S NBT" Bearings are magnetic.



Signed by Stephan J. Szyszkoski
Surveyor's Michigan License No. 33986

Date 10/15/2009

For the Michigan Department of Natural Resources, Office of Land and Facilities