

CHIPPEWA COUNTY REMONUMENTATION CORNER
LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

MAR 27 1996

COMMISSION

For corners in

Chippewa
(County)

Located in:

Corner Code #

1. Public Land Survey

T46N R2W

C-137 Same

T45N R2W

C-1 Corner

T R

T R

T R

2. Property Controlling
In Section

S T R

S T R

3. Miscellaneous
Property in Sec.

S T R

S T R

\$ 7.00 LAND CORNER

\$ 2.00 HSSR

29 FEB 96 9:28 A.M. RECEIPT# 462

RECEIVED FOR RECORD

CHIPPEWA COUNTY - STATE OF MICHIGAN
SHARON H. KENNEDY, REGISTER OF DEEDS

Register of Deeds Stamp & File Number

4. Lot No. , Recorded Plat

5. Private Claims

I, Larry R. Rogers, in a field survey on October 23 1995 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and for that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

	A	B	C	D	E	F	G	H	I	J	K	L	M
1													
2	6		5		4		3		2		1		
3													
4	7		8		9		10		11		12		
5													
6	18		17		16		15		14		13		
7													
8	19		20		21		22		23		24		
9													
10	30		29		28		27		26		25		
11													
12	31		32		33		34		35		36		
13													

A. Description of original monument and accessories and/or subsequent restoration:
(C-13) Southwest Corner of Section 32.

1840: Austin Burt "set post corner of Sections 31 and 32" with the following witnesses:
10" Fir N33E 17 links 7" Fir N29W 30 links

1990: Gerald L. Wiggins, P.S. 23521. "Set corner at found iron pin in center line of North and South road", and recorded in Liber 7, Page 245 of the Chippewa County Corner Records with the following witnesses:

7" Red Pine S63°E 37.7' 10" Spruce N25°W 71.3'
6" Spruce N42°E 79.9' 8" Spruce N84°E 52.3'

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:


(C-13) This corner is being perpetuated as part of the Chippewa County Remonumentation Program.

Found no evidence of original corner position. Found 3/4" iron with D.N.R. plastic cap in centerline of Tilson Road (corner form calls for 1" iron pipe). Recovered four existing witnesses in good shape. Reblazed and set nails in side of trees.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

(C-13) Corner is 3/4" iron pin with plastic D.N.R. cap in centerline of Tilson Road (North-South gravel).

Witnesses: 9" Spruce N42°E 80.10'
8" Red Pine S63°E 38.14'
10" Spruce N84°W 52.78'
12" Spruce N25°W 71.81'
Wood Post East 24.33'



Signed by [Signature]

Surveyor's Michigan License No. 29251

NOTE: All bearings are compass bearings corrected for declination. All distances are to a nail in side of witness objects unless otherwise noted.

FORM APPROVED BY MICHIGAN STATE BOARD OF PROFESSIONAL SURVEYORS, JAN. 28, 1971
REVISED MAY 14, 1975
REVISED JAN., 1983
REVISED OCT., 1995