

SURVEY &
REMONUMENTATION

FEB 18 1994

CLARE COUNTY REMONUMENTATION PROGRAM

COMMISSION

LAND CORNER RECORDATION CERTIFICATE

Filing Requirement of Act 74, Mich. P.A. 1970

For corners in

CLARE
(County)

Located In:

Corner Code ##

1. Public Land Survey

T 17N R 6W

E-7

2. Property Controlling
in Section

S T R

3. Miscellaneous
Property in Sec.

S T R

4. Lot No. , Recorded Plat

5. Private Claims

Register of Deeds Stamp & File Number

I, MARK R. ROBISON, in a field survey on OCTOBER, 19 93,
do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned
in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the
current manual of survey instructions of the United States Department of the Interior, Bureau of Land
Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5
above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a
Court of Law; established, re-established, monumented, re-monumented, recovered, found as
expressed below:

**NOTE: Not more than 4 corners, all in the same town and range, may be recorded
on this certificate.**

A. Description of original monument and accessories and/or subsequent restoration:

1847 ORSON LYON, POST, W. OAK 13" S 65-1/4°W, 42 LKS P. 333
PINE 12" N 40-1/2°E, 35-1/2 LKS

6-16-08 A. JOHNSON, CSR 4-142
CSR 6-165

11-06-73 LAPHAM, LCRC 119-73

12-07-76 McCLUNG, LCRC 453-84

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

FOUND 1-1/2" PIPE IN BADLY RUSTED CONDITION AND WOOD STAKE (RELATIVELY NEW). WITNESSES FIT STAKE.
DUG 3' DEEP. PIPE WAS STILL IN SOLID CONDITION BUT BADLY RUSTED AND BENT DUE TO OUR DIGGING EFFORTS
AS WELL AS BENT APPARENTLY FROM PREVIOUS EFFORTS. DECIDED TO LEAVE PIPE (BROKEN OFF ABOUT 12"
BELOW GRADE) AND RAISE WITH 5/8" x 36" RE-BAR SET ALONG SIDE OF PIPE AT BOTTOM OF HOLE, AND
IN POSITION OF TOP OF PIPE.

FOUND RECORDED WITNESSES:

N 10°E, 34.23' - 6" OAK TREE
S 55°E, 61.24' - 18" OAK TREE
S 52°E, 61.20' - 20" RED OAK
SOUTH, 34.0' - STEEL FENCE POST

This Corner established in Clare County Remonumentation Program.
See dossier for detailed report.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

SET 5/8" x 36" RE-ROD WITH 3" CLARE COUNTY MONUMENT CAP.

SOUTH, 34.10' - 3" STEEL FENCE POST
S 55°E, 61.17' - 24" OAK TREE
N 10°E, 34.27' - 14" OAK TREE
N 47°W, 73.45' - 14" OAK TREE



Signed by

Mark R. Robison

Date

11/30/93

Surveyor's Michigan License No.

27458