

MAR 27 1996

COMMISSION

LAND CORNER RECORDATION CERTIFICATE

Filing Requirement of Act 74, Mich. P.A. 1970

For corners in
Crawford

(County)

Located In:

Corner Code #

STATE OF MICHIGAN
CRAWFORD COUNTY
RECORDED

27 DEC 95 3:00 P.M.

SANDRA NOORE
REGISTER OF DEEDS

1. Public Land Survey T 26N R 3W C - 2
T R
T R
T R
2. Property Controlling S T R
in Section S T R
3. Miscellaneous S T R
Property in Section S T R

Register of Deeds Stamp & File Number

4. Lot No. , Recorded Plat
5. Private Claims

I, Marvin E. Myers, in a field survey on December 13, 19 95, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Professional Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

GLO-James Mullett
Mon.-Set Post
WIT: 8" Cedar N34°E 31 lks.
9" Cedar S45°W 13 lks.

R. Ostling May 1946
Mon.-Set 3/4" Pipe for 1/4 Cor.
WIT: 6" Cedar N56°E 24.10'
8" W.Birch N84°W 36.90'

N. Parker June 1977 L.2, pg.143
Mon.-PK Nail in Black top over 3/4" Pipe
used by local surveyors in previous
surveys of record
WIT: B.T. 16" Birch N84°W 36.90'
Face of P.Pole N25°E 90.40'
Plat Mon. N87°10'E 33.00'

LIBER 3 PAGE 225

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:


Found PK nail over 3/4" pipe. Found B.T. 16' White Birch with nail in side with blaze on face.
Replaced PK with standard monument and placed in pavement monument box. Found concrete monument NORTH PARK
PLAT N86°W 33.00'.

CRAWFORD COUNTY
PEER GROUP APPROVAL
DATE DEC 19, 1995

Marvin E. Myers
Marvin E. Myers, P.S.
County Surveyor

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

Mon.-Standard Crawford County Monument in pavement monument box
WIT: Set nail & tag S. side 6" Cedar N72°W 36.54'
Set nail & tag NW side 4" B.Spruce S59°W 36.40'
Fd. spike in NE side 5" Poplar S31°E 55.45'
Fd. spike in S. side 4" Poplar N72°E 39.84'



Signed by Marvin E. Myers

Date Dec 21, 1995

Surveyor's Michigan License No. 31600

FORM APPROVED BY MICHIGAN STATE BOARD OF PROFESSIONAL SURVEYORS, JAN. 28, 1971
REVISED MAY 14, 1975
REVISED JAN., 1983