

SURVEY & REMONUMENTATION

FEB 04 1999

SECTION

LAND CORNER RECORDATION CERTIFICATE Filing Requirement of Act 74, Mich. P.A. 1970

STATE OF MICHIGAN
COUNTY OF CHARLEVOIX
RECEIVED FOR RECORD

98 NOV 13 PM 3:57

For corners in
CHANDLER TWP

CHARLEVOIX
(County)

Located In:

Corner Code #

Charles M. Probert
REGISTER OF DEEDS

1. Public Land Survey T 33N R 4 W M-4
T R
T R
T R
2. Property Controlling S T R
in Section S T R
3. Miscellaneous S T R
Property in Sec. S T R

Register of Deeds Stamp & File Number

4. Lot No. , Recorded Plat

5. Private Claims

I, JAMES E. EVANS, in a field survey on OCTOBER 5, 1998
do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points
mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as
required in the current manual of survey instructions of the United States Department of the Interior,
Bureau of Land Management or by a decree of a Court of Law and /or that the corner points
mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of
Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented,
recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded
on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:
M-4 QUARTER CORNER COMMON TO SEC 12 T33N-R4W & SEC 7 T33N-R3W
GENERAL LAND OFFICE
Set 1/4 Sec. post
Maple 20" S09°W 17 Links (11.22')
Ash 8" N02°E 17 Links (11.22')
May 22, 1840
By: John Mullett D.S.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:
M-4 QUARTER CORNER COMMON TO SEC 12 T33N-R4W & SEC 7 T33N-R3W

Found no corner or evidence of original corner.
No occupation available.

Distance to corner M-3 Measured 2657.20' (GLO = 2640.0')
Distance to corner M-5 Measured 2657.20' (GLO = 2640.0')

Charlevoix Co. Surveyor
APPROVED
Signature Mary C. Fennell
Date: Nov. 12, 1998

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:
M-4 QUARTER CORNER COMMON TO SEC 12 T33N-R4W & SEC 7 T33N-R3W

Set cast iron Charlevoix County monument half way on line between M-3 and M-5.


WITNESSES: 18" R. Pine S18°E 36.73' Set nail and cap in West side
11" Maple S34°W 30.89' Set nail and cap in East side
10" Maple N75°W 32.69' Set nail and cap in NW side
20" R. Pine S59°E 33.06' Set nail and cap in SW side

And is accepted as the best available evidence of the position of the original corner.

Signed by James E. Evans
Surveyor's Michigan License No. 22431

Date 11-12-98

003 204



APPROVED BY MICHIGAN STATE BOARD OF PROFESSIONAL SURVEYORS, JAN. 28, 1971.
REVISED MAY 14, 1975
REVISED JAN., 1983
REVISED OCT., 1985