

SURVEY & REMONUMENTATION

MAY 05 1997

COMMISSION

LAND CORNER RECORDATION CERTIFICATE 1996 DEC 18 AM 11:15
Filing Requirement of Act 74, Mich. P.A. 1970

For corners in

<u>Dickinson</u> (County)	Located In:	Corner Code #
1. Public Land Survey	T <u>40N</u> R <u>28W</u>	M-10*
	T <u>40N</u> R <u>28W</u>	<u>A-10</u>
	T _____ R _____	_____
	T _____ R _____	_____
2. Property Controlling in Section	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____
3. Miscellaneous Property in Sec.	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____

REGISTER OF DEEDS
DICKINSON COUNTY
IRON MOUNTAIN, MI 49801

14

Register of Deeds Stamp & File Number

4. Lot No. _____, Recorded Plat _____
5. Private Claims _____

I, Michael Mileski, in a field survey on 21 November 19 96 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

M-10; East One-quarter Corner Section 25, T40N, R29W;

See back of form.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

M-10; East One-quarter Corner Section 25, T40N, R29W;

Found a circular rock collar 18" in diameter at ground level. Several feet away Mr. Buckler's monument was recovered on its side and completely buried. This area was clearcut in the past and it is obvious that Mr. Buckler's monument was victimized by a skidder blade. As mentioned in Part A, the remains of Mr. Buckler's balsam new bearing tree are located at the proper position. Set a standard county monument in the center of the rock collar 12" into the ground and rebuilt the rock collar. Accepted as a careful and faithful perpetuation of the position of the original corner.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

M-10; East One-quarter Corner Section 25, T40N, R29W;

Set a 5/8" x 36" aluminum rod with a 3" aluminum cap stamped as to location and constructed a rock collar measuring 2.5' east and west, 2' north and south, and 2' in height.

Set 7" spike	E/side	5" Balsam	N38°E	60.10'
Set 7" spike	S/side	7" Aspen	S87°E	30.74'
Set 7" spike	E/side	7" Aspen	S19°W	6.93'
Set 7" spike	SE/side	12" Balsam	S48°W	20.15'
Set 7" spike	N/side	4" Balsam	S73°W	44.60'
Set 7" spike	W/side	7" Aspen	N16°W	12.10'
		Location Post	North	4.0'

All of the above new bearing trees are marked with upper and lower blazes. The lower blaze is scribed "NBT". Both blazes as well as a band around the tree at the upper blaze are painted red.

*This corner is also A-10 of T40N, R28W.

Signed by Michael Mileski
Surveyor's Michigan License No. 39091

Date 3 Dec 1996
Bk. 17M pp 26 & 27

1	A	B	C	D	E	F	G	H	I	J	K	L	M
2		6		5		4		3		2		1	
3													
4		7		8		9		10		11		12	
5													
6		18		17		16		15		14		13	
7													
8		19		20		21		22		23		24	
9													
10		30		29		28		27		26		25	
11													
12		31		32		33		34		35		36	
13													

ACCEPTED BY THE DICKINSON COUNTY
SURVEY PEER GROUP AS THE C. AL
CORNER UNDER MICHIGAN P. CT
345 OF 1990 AT A M. T. A. UN
12-17-96
RSP
COUNTY REPRESENTATIVE

