

MAY 07 1997

RECORDED

**COMMISSION LAND CORNER RECORDATION CERTIFICATE** 1996 DEC 18 AM 11:16  
Filing Requirement of Act 74, Mich. P.A. 1970

For corners in

Dickinson  
(County)

Located In:

Corner Code #

REGISTER OF DEEDS  
DICKINSON COUNTY  
IRON MOUNTAIN, MI 49801

- |                                    |                           |       |
|------------------------------------|---------------------------|-------|
| 1. Public Land Survey              | T <u>40N</u> R <u>29W</u> | F-7   |
|                                    | T _____ R _____           | _____ |
|                                    | T _____ R _____           | _____ |
|                                    | T _____ R _____           | _____ |
| 2. Property Controlling in Section | S _____ T _____ R _____   | _____ |
|                                    | S _____ T _____ R _____   | _____ |
| 3. Miscellaneous                   | S _____ T _____ R _____   | _____ |
| Property in Sec.                   | S _____ T _____ R _____   | _____ |

(2)

Register of Deeds Stamp & File Number

4. Lot No. \_\_\_\_\_, Recorded Plat \_\_\_\_\_  
5. Private Claims \_\_\_\_\_

I, Michael Mileski, in a field survey on 29 October, 19 96 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and /or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

F-7; One-quarter Corner common to Sections 16 and 21, T40N, R29W;

See back of form.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

F-7; One-quarter Corner common to Sections 16 and 21, T40N, R29W;

Found a 1" x 42" galvanized iron pipe with a 4" brass cap, firmly set, as established by Mr. Buckler in 1955, projecting 20 inches above the ground alongside of which is a 2" x 2" squared wood post marked "¼ 16 \ 21" firmly set and projecting 4 feet above the ground. Replaced Mr. Buckler's monument with a standard county monument described in Part C. Accepted as a careful and faithful reestablishment of the position of the original corner.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

F-7; One-quarter Corner common to Sections 16 and 21, T40N, R29W;

Set a 5/8" x 36" aluminum rod with a 3" aluminum cap stamped as to location projecting 4" above the ground.

Set 7" spike	NW/side	7" Sugar Maple	N45°E	33.20'
Set 7" spike	N/side	7" Sugar Maple	S84°E	29.31'
Set 7" spike	E/side	8" Sugar Maple	South	41.30'
Set 7" spike	N/side	7" Sugar Maple	N75°W	55.36'
		Location Post	North	3.0'

All of the above new bearing trees are marked with upper and lower blazes.

The lower blaze is scribed "NBT". Both blazes as well as a band around the tree at the upper blaze are painted red.



Signed by Michael Mileski  
Surveyor's Michigan License No. 39091

Date 3 DEC 1996

Bk. 17M pp 14 & 15