

MAY 07 1997

COMMISSION

LAND CORNER RECORDATION CERTIFICATE  
Filing Requirement of Act 74, Mich. P.A. 1970

RECORDED

1996 DEC 18 AM 11:17

For corners in

DICKINSON  
(County)

Located In:

Corner Code #

WAUCEDAH TWP.

1. Public Land Survey T 41N R 27W  
T \_\_\_\_\_ R \_\_\_\_\_  
T \_\_\_\_\_ R \_\_\_\_\_  
T \_\_\_\_\_ R \_\_\_\_\_
2. Property Controlling S \_\_\_\_\_ T \_\_\_\_\_ R \_\_\_\_\_  
in Section S \_\_\_\_\_ T \_\_\_\_\_ R \_\_\_\_\_
3. Miscellaneous S \_\_\_\_\_ T \_\_\_\_\_ R \_\_\_\_\_  
Property in Section S \_\_\_\_\_ T \_\_\_\_\_ R \_\_\_\_\_

H-13  
G-13

REGISTER OF DEEDS  
DICKINSON COUNTY  
IRON MOUNTAIN, MI 49801

25

Register of Deeds Stamp & File Number

4. Lot No. \_\_\_\_\_, Recorded Plat \_\_\_\_\_
5. Private Claims \_\_\_\_\_

I, ROBERT F. PERKINS, in a field survey on 10-14, 19 96, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Professional Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

H-13 SOUTH  $\frac{1}{4}$  CORNER SECTION 34  
 $\frac{1}{4}$  POST BY AUSTIN BURT, D.S. 1846  
ORIGINAL BEARING TREES  
SUGAR 6" N71°E 46 L.  
SUGAR 9" N45°W 11 L.  
V=10°45'E

G-13 STANDARD CORNER BETWEEN SECTIONS 33 & 34  
POST BY AUSTIN BURT, D.S. 1846  
ORIGINAL BEARING TREES  
SUGAR 18" N24°E 42 L.  
HEMLOCK 14" N32°W 35 L.

	A	B	C	D	E	F	G	H	I	J	K	L	M
2	6		5		4		3		2		1		
3													
4	7		8		9		10		11		12		
5													
6	18		17		16		15		14		13		
7													
8	19		20		21		22		23		24		
9													
10	30		29		28		27		26		25		
11													
12	31		32		33		34		35		36		
13													

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

H-13 NO EVIDENCE OF ORIGINAL CORNER OR ACCESSORIES FOUND.  
FOUND 1" IRON PIPE WITH 4"  
K.C. CORP. BRASS CAP SET BY  
N. SPERHAK 11-30-62. (REPORT #679)  
1962 BEARING TREES  
W. ASH 8" N4°E 27 L.  
IRONWOOD 7" N24°W 27 L.

G-13 NO EVIDENCE OR ORIGINAL CORNER OR ACCESSORIES FOUND.  
CORNER WAS RESTORED AND MONUMENTED BY N. SPERHAK IN ABOUT 1961 (REPORT #30). THIS CORNER HAS BEEN LOST-PROBABLY DUE TO ROAD CONSTRUCTION. DETERMINED LOCATION OF SPERHAK'S CORNER BY TRAVERSING WEST FROM H-13 AND CLOSING 1/16 CORNER. ACCEPTED BY THE DICKINSON COUNTY SURVEY PEER GROUP AS THE OFFICIAL CORNER UNDER MICHIGAN PUBLIC ACT 346 OF 1960 AT A MEETING HELD ON

12-17-96  
RFP

COUNTY REPRESENTATIVE

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

H-13 FOUND ABOVE MONUMENT AND BEARING TREES IN PLACE.  
NEW BEARING TREES:  
MAPLE 12" S47°W (M.B.) 10.56' NAIL/TAG  
MAPLE 6" N37°W (M.B.) 10.55' NAIL/TAG  
LYNN 18" N6°E (M.B.) 17.45' NAIL/TAG  
MAPLE 5" S35°E (M.B.) 14.30' NAIL/TAG


G-13 SET 2 $\frac{1}{2}$ " D.C. REMON. STAMPED CAP AT RESTORED LOCATION OF SPERHAK'S CORNER.  
NEW WITNESSES:  
MAPLE 6" N74°E (M.B.) 3.65' NAIL/TAG  
MAPLE 8" S40°W (M.B.) 14.73' NAIL/TAG  
MAPLE 5" S83°W (M.B.) 14.34' NAIL/TAG  
CENTERLINE STEEL GATE POST N47°E (M.B.) 44.81'  
PLACED CARSONITE MARKER 1' NORTH OF CORNER.

Signed by Robert F. Perkins

Date NOVEMBER 6, 1996

Surveyor's Michigan License No. 12027

FORM APPROVED BY MICHIGAN STATE BOARD OF PROFESSIONAL SURVEYORS, JAN 28, 1997



Liber 2

Page 272