

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970 as Amended

For corners in

Dickinson Located In: Corner Code #
1. Public Land Survey
2. Property Controlling Section
3. Miscellaneous Property in Sec.
4. Lot No. Recorded Plat
5. Private Claims

2/12/2013AD
Jeremy J. Pipp, in a field survey on 2/12/2013AD do hereby state
that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and /or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

(03) North One-Sixteenth corner common to Sections 28 and 29. Not set in original survey, no evidence of subsequent establishment.

(05) Center-North One-Sixteenth corner of Section 28. Not set in original survey, no evidence of subsequent establishment.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

(03) Corner position established mid-point and on-line between the West One-Quarter corner and the Northwest corner of Section 28.


(05) Corner position established mid-point and on-line between the Center One-Quarter corner and the North One-Quarter corner of Section 28.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

(03) DNR monument
6" Elm N35E 37.95' (1/16S,BT)
13" Spruce S63E 42.93' (1/16S,BT)
9" Elm S23W 19.01' (1/16S,BT)
8" Tw. Maple N61W 34.68' (1/16S,BT)
All trees are blazed, scribed, and painted. Measurements are to nail in side of tree, bearings are magnetic.

Signed by
Surveyor's Michigan License No.

(05) DNR monument
7" Tamarack North 15.30' (1/16S,BT)
4" Tamarack S74E 20.69' (1/16S,BT)
8" Tamarack S68W 11.52' (1/16S,BT)
5" Tamarack N72W 15.19' (1/16S,BT)
All trees are blazed, scribed, and painted. Measurements are to nail in side of tree, bearings are magnetic.



July 18, 2013

For the Michigan Department of Natural Resources, Forest Resource Division

Table with 13 rows and 13 columns (A-M). Contains numbers 1-36 and a grid for Register of Deeds Stamp & File Number.