

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970 as Amended

For corners in

Dickinson	Located In:	Corner Code #
(County)		
Norway Township		
1. Public Land Survey	T _____ R _____	_____
	T _____ R _____	_____
	T _____ R _____	_____
2. Property Controlling in Section	S 8 T 41N R 29W	9
	S 8 T 41N R 29W	13
	S _____ T _____ R _____	_____
3. Miscellaneous Property in Sec.	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____
4. Lot No. _____, Recorded Plat _____		
5. Private Claims _____		

Register of Deeds Stamp & File Number

	A	B	C	D	E	F	G	H	I	J	K	L	M
1													
2	5		5		4		3		2		1		
3													
4	7		8		9		10		11		12		
5													
6	18		17		16		15		14		13		
7													
8	19		20		21		22		23		24		
9													
10	30		29		28		27		26		25		
11													
12	31		32		33		34		35		36		
13													

I, Jeremy J. Pipp, in a field survey on 6/26/2012AD do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey Instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and /or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

(09) Center-East One-Sixteenth corner of Section 8. Not set in original survey, no evidence of subsequent establishment.

(13) Southeast One-Sixteenth corner of Section 8. Not set in original survey, no evidence of subsequent establishment.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

(09) Corner position established mid-point and on-line between the Center One-Quarter corner and the East One-Quarter corner of Section 8. Monument set in notched out base of Maple tree.

(13) Corner position established at the intersection of the South and East One-Sixteenth lines of Section 8.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

(09) DNR monument
7" Tw. Maple NE 0.55' (1/16S,BT)
6" Spruce S66E 25.80' (1/16S,BT)
5" Maple S47W 30.50' (1/16S,BT)
6" Tri. Maple N59W 36.54' (1/16S,BT)
All trees are blazed, scribed, and painted. Measurements are to nail in side of tree, bearings are magnetic.

(13) DNR monument
4" White Pine N24E 26.40' (1/16S,BT)
7" Cedar S10E 31.05' (1/16S,BT)
21" White Pine S17W 36.95' (1/16S,BT)
12" Cedar N83W 35.86' (1/16S,BT)
All trees are blazed, scribed, and painted. Measurements are to nail in side of tree, bearings are magnetic.


Signed by Jeremy J. Pipp July 18, 2012

Surveyor's Michigan License No. 50447

For the Michigan Department of Natural Resources, Professional Surveyors and Geomatics

20082

20081



APPROVED BY THE MICHIGAN STATE BOARD OF PROFESSIONAL SURVEYORS, JAN. 28, 1971
Revised May 14, 1975
Revised Jan., 1983
Revised Oct., 1995