

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970 as Amended

For corners in

Dickinson Located In: Corner Code #
NORWAY TOWNSHIP
1. Public Land Survey T 41N R 29W K05
2. Property Controlling in Section S 13 T 41N R 29W 04
3. Miscellaneous Property in Sec. S T R

4. Lot No. , Recorded Plat
5. Private Claims

2/14/2013AD
Jeremy J. Pipp, in a field survey on 2/14/2013AD do hereby state
that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2
above were in conformance with regulations and rules therefore as required in the current manual of survey
instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of
a Court of Law and /or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with
the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established,
re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded
on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

(K05) Corner common to Sections 11, 12, 13, and 14. 1849: John Burt, DS. Set Cedar post
witnessed by: Cedar 24 N67W 17 links (11.22'); Cedar 14 S54E 15 links (9.90'); 1959: Michigan
DNR (Billy Buckler PS#8887) Set 1" pipe with 4" Brass cap witnessed by 8" Maple N47W 27 links
(17.82'), 8" Maple N43E 37 links (24.42'). 1993: Ewart Muller (PS#15408)[LCRC Liber 2, page 73]
found MDNR monument and witnessed : Maple 10 N47W 18.25', Maple 12 N44E 24.75', Maple 7 East
34.40', Squared Maple 13 S42W 1.90' .

(04) Northwest One-Sixteenth corner of Section 13. Not set in original survey, no
evidence of subsequent establishment.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

(K05) Accepted found MDNR Monument and Three existing NBT Witnesses. Left MDNR monument
in place and re-witnessed. Accepted found MDNR Monument and Witness remains as a careful
and faithful REESTABLISHMENT of the position of the original corner.

(04) Corner position established at the intersection of the North and West One-
Sixteenth lines of Section 13.


C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

(K05) DNR monument
EX. 12" Maple N43E 24.84' (S12,NBT)
7" Maple S83E 30.41' (S13,NBT)
EX. 14" Maple S36W 1.85' (S14,NBT)
EX. 9" Maple N22W 18.29' (S11,NBT)
All trees are blazed, scribed, painted,
and signed. Measurements are to nail in
side of tree, bearings are magnetic. A
Carsonite rail was set North 1.5 feet.

Signed by
Surveyor's Michigan License No. 50447

(04) DNR monument
4" Ironwood N83E 35.57' (1/16S,BT)
4" Ironwood S74E 51.48' (1/16S,BT)
12" Poplar S18W 30.35' (1/16S,BT)
9" Maple N39W 22.90' (1/16S,BT)
All trees are blazed, scribed, and
painted. Measurements are to nail in
side of tree, bearings are magnetic.

Date July 22, 2013



For the Michigan Department of Natural Resources Files and Records Division