

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970 as Amended

For corners in

Dickinson (County) Located In: Corner Code #
1. Public Land Survey
2. Property Controlling Section
3. Miscellaneous Property in Sec.

4. Lot No. Recorded Plat
5. Private Claims
2/21/2013AD
Jeremy J. Pipp, in a field survey on 2/21/2013AD do hereby state

that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and /or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

(07) North One-Sixteenth corner common to Sections 15 and 16. Not set in original survey, no evidence of subsequent establishment.

(15) West One-Sixteenth corner common to Sections 16 and 21. Not set in original survey, no evidence of subsequent establishment.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

(07) Corner position established mid-point and on-line between the East One-Quarter corner and the Northeast corner of Section 16.

(15) Corner position established mid-point and on-line between the South One-Quarter corner and the Southwest corner of Section 16.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

(07) DNR monument
4" Maple N05E 9.60' (1/16S,BT)
6" ELM S59E 15.35' (1/16S,BT)
5" ELM S08W 32.81' (1/16S,BT)
5" ASH N33W 41.05' (1/16S,BT)
All trees are blazed, scribed, and painted. Measurements are to nail in side of tree, bearings are magnetic.
(15) DNR monument
25" Cedar N04E 25.94' (1/16S,BT)
14" Cedar N39E 17.65' (1/16S,BT)
5" Cherry S15E 5.96' (1/16S,BT)
11" Maple S16W 39.51' (1/16S,BT)
All trees are blazed, scribed, and painted. Measurements are to nail in side of tree, bearings are magnetic.

Signed by [Signature] JEREMY J. PIPP Date July 22, 2013
Surveyor's Michigan License No. 50447 PROFESSIONAL SURVEYOR

For the Michigan Department of Natural Resources, Forest Resources Division




Table with 13 rows and 13 columns (A-M) for Register of Deeds Stamp & File Number. Contains numerical data for each cell.