

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970 as Amended

For corners in

Dickinson	Located In:	Corner Code #
(County)		
Felch Township		
1. Public Land Survey	T _____ R _____	_____
	T _____ R _____	_____
	T _____ R _____	_____
2. Property Controlling in Section	S 14 T 42N R 29W	6
	S 22 T 42N R 29W	7
	S _____ T _____ R _____	_____
3. Miscellaneous Property in Sec.	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____
4. Lot No. _____, Recorded Plat _____		
5. Private Claims _____		

Register of Deeds Stamp & File Number

	A	B	C	D	E	F	G	H	I	J	K	L	M
1													
2	5		5		4			3		2			1
3													
4	7		8		9			10		11			12
5													
6	10		17		16			15		14			13
7													
8	19		20		21			22		23			24
9													
10	30		29		28			27		26			25
11													
12	31		32		33			34		35			36
13													

I, Jeremy J. Pipp, in a field survey on 8/06/2012AD do hereby state
that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2
above were in conformance with regulations and rules therefore as required in the current manual of survey
instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of
a Court of Law and /or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with
the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established,
re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded
on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

(06) Northeast One-Sixteenth corner of Section 14. Not set in original survey, no evidence of
subsequent establishment.

(07) North One-Sixteenth corner common to Sections 22 and 23. 1977: Michigan DNR (Arthur Enger
PS#13581) set DNR monument witnessed by: 7" Black Ash S62E 6.0', 6" Cedar S64W 34.1', Top Center
of S. end of Culvert N62W 1.90'; 1993: Michigan DNR (Stephan Szyszkoski PS#33986) found DNR
monument added witnesses: 11" Black Ash S48E 10.4', 8" Black Ash S12W 26.0'; 2008: Steven
Applekamp PS#43045 Set 5/8 inch Rebar, previous monument not found.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

(06) Corner position established at the intersection of the North and East One-Sixteenth
lines of Section 14. Drilled hole into boulder, set rebar and capped with aluminum MDNR
monument

(07) Found 5/8" rebar and remains of two BT's (dead Ash S24E 25.46' & dead Cedar S60W
33.13'). It appears that the roadway had been raised sometime between 1993 & 2008;
corner is 2.5' South of South Edge of Bit and +/-2 ft east of N-S culvert & about 20
feet north of ditch/end of culvert. Position is accepted as a careful and faithful
PERPETUATION of the position of the original corner.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

(06) DNR monument (in rock)
4" Ironwood N12E 15.35' (1/16S,BT)
4" Maple S60E 13.80' (1/16S,BT)
6" Maple S29W 20.48' (1/16S,BT)
5" Maple N81W 39.21' (1/16S,BT)
All trees are blazed, scribed, and
painted. Measurements are to nail in
side of tree, bearings are magnetic.

(07) DNR monument
Stop Sign S85E 207.30' (- , -)
1" Pipe S05W 33.00' (- , -)
Tele. Ped. Post S85W 88.68' (- , -)
Powerpole 45-5 N33W 40.93' (- , -)
All witnesses are painted. Measurements
are to be in side of post & powerpole,
bearings are magnetic.

Signed by Jeremy J. Pipp
Surveyor's Michigan License No. 50447

For the Michigan Department of Natural Resources



Date August 29, 2012

20112

20115

FORM APPROVED BY MICHIGAN STATE BOARD OF PROFESSIONAL SURVEYORS, JAN. 28, 1971
Revised May 14, 1975
Revised Jan., 1983
Revised Oct., 1995