

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970 as Amended

or corners in

Form with fields for Dickinson (County), Located In, Corner Code #, Public Land Survey, Property Controlling Section, Miscellaneous Property in Sec., Lot No., Recorded Plat, Private Claims.

Register of Deeds Stamp & File Number

Table with 13 rows and 13 columns (A-M) for Register of Deeds Stamp & File Number.

Jeremy J. Pipp, in a field survey on 6/24/2014 do hereby state
that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2
above were in conformance with regulations and rules therefore as required in the current manual of survey
structions of the United States Department of the Interior, Bureau of Land Management or by a decree of
Court of Law and /or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with
the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established,
re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded
in this certificate.

1. Description of original monument and accessories and/or subsequent restoration:

(E06) Quarter corner common to Sections 16 and 17. 1849: John Burt, DS. Set elm post
witnessed by: Elm 6 N34E 40 lks.; Y.Birch 12 S44W 15 lks. 1977: Art Enger, RLS. Set
DNR monument by single proportion between the southeast corner and the calculated double
proportion position of the northeast corner of Section 17 witnessed by: Sugar Maple 9
S49E 37.7'; Elm 9 N52W 15.6' 2008: Michigan DNR (Paul Bressette, PS#37270) accepted
found monument and added witnesses: 13" Spruce N86E 40.5' (1/4S,NBT), 15" Maple S46E
37.75' (EX. NBT), 09" Elm S02E 14.35' (1/4S,NBT), 06" Elm N82W 12.2' (1/4S,NBT).

2. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

(E06) As noted in previous Michigan DNR (Paul Bressette, PS#37270) LCRC: "Found Enger's
monument and witnesses as described. Sugar is live and standing, Elm is dead and down.
Enger considered the existing monument set at the northeast corner of Section 17 to have
been erroneously set due to insufficient evidence. However, due to its use to establish
corners west, he determined it best not to disturb its position but to use the double
proportion position to reestablish this corner (and others) and not extend the error into
his survey. A full explanation can be found in Enger's corner record for corner E4. In
order to not disturb existing surveys, monument was rewitnessed as found, and is accepted
as a careful and faithful REESTABLISHMENT of the position of the original corner." (Note
Two of Bressettes NBT's were standing dead, thus this position was rewitnessed).

3. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

(E06) DNR monument
7" Balsam N37E 15.14' (1/4S,NBT)
EX 16" Maple S50E 37.76' (1/4S,NBT)
EX 11" Maple S03W 14.35' (1/4S,NBT)
5" Cherry N79W 39.41' (1/4S,NBT)
All trees are blazed, scribed, painted,
and signed. Measurements are to nail in
side of tree, bearings are magnetic. A
Carsonite rail was set South 1.5 feet.

Signed by [Signature] Date July 15, 2014
Surveyor's Michigan License No. 50447



For the Michigan Department of Natural Resources, Forest Resources Division