

DEC 16 1996

FILED  
Copy

COMMISSION

LAND CORNER RECORDATION CERTIFICATE  
Filing Requirement of Act 74, Mich. P.A. 1970

96 OCT 30 PM 1:45

For corners in

Eaton Located in: Corner Code #  
 (County)  
Walton Township  
 1. Public Land Survey T/W R SW L-6  
 T R  
 T R  
 T R  
 T R  
 2. Property Controlling S T R  
 in Section S T R  
 3. Miscellaneous S T R  
 Property in Sec. S T R  
 4. Lot No. \_\_\_\_\_, Recorded Plat \_\_\_\_\_  
 5. Private Claims \_\_\_\_\_

LINDA M. TWITCHELL  
REGISTER OF DEEDS  
EATON COUNTY, MICH.

Liber 3 pg 729

Register of Deeds Stamp & File Number

I, David R. Lohr, in a field survey on Sept. 17, 1996 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

	A	B	C	D	E	F	G	H	I	J	K	L	M
1													
2	6		5		4		3		2		1		
3													
4	7		8		9		10		11		12		
5													
6	18		17		16		15		14		13		
7													
8	19		20		21		22		23		24		
9													
10	30		29		28		27		26		25		
11													
12	31		32		33		34		35		36		
13													

A. Description of original monument and accessories and/or subsequent restoration:

- L-6: 1. CORNER NOT SET IN ORIGINAL GOVERNMENT SURVEYS.  
 2. CORNER REFERENCED IN SURVEY BY WM. SIMPSON, COUNTY SURVEYOR, DATED NOV. 1871 AND RECORDED IN VOL. 1 PG. 150-151. AS "STAKE". WITNESSED BY ELM 20 S 31 W 06 1/2 LKS (4.29')  
 3. NO OTHER REFERENCES FOUND.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

- L-6: VISITED APPARENT LOCATION OF CORNER AND FOUND REMAINS OF ANCIENT WOOD ANCHOR POST AT INTERSECTION OF FENCES NORTH-SOUTH AND EAST-WEST. SET IRON ALONG WEST SIDE OF ANCHOR POST REMAINS ABOUT 1.3' WEST OF FENCE LINES INTERSECTION. TRAVERSED SECTION 13 AND FOUND THIS IRON TO BE 0.27' SOUTH AND 4.89' EAST OF THE INTERSECTION OF THE 1/4 LINES. ACCEPTED IRON AS CORNER BASED ON RECORD OF SURVEY BY SIMPSON, AND SET 3/4" X 24" STANDARD REMON. BAR/PA #345 CAP #30090 ALONG WEST SIDE OF THE REMAINS OF THE OLD POST.  
 MEASURED 2672.36' EAST TO M-5. MEASURED 2664.25' SOUTH TO L-7.  
 MEASURED 2674.45' WEST TO L-5. MEASURED 2644.75' NORTH TO L-5.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

- L-6: SET 3/4" X 24" STANDARD REMON. BAR / PA#345 CAP #30090 ALONG THE WEST SIDE OF THE REMAINS OF AN ANCIENT WOOD ANCHOR POST. WITNESSED BY:  
 SET NAIL/TAG #30090 E/S 5" MAPLE, AZ. 23 DEG., 19.54'  
 SET NAIL/TAG #30090 S/S 6" MAPLE, AZ. 70 DEG., 9.60'  
 SET NAIL/TAG #30090 N/S TW. 15" ASH, AZ. 131 DEG., 10.40'  
 SET NAIL/TAG #30090 N/S 4" MAPLE, AZ. 248 DEG., 6.38'  
 TRAV. PT. #WL2-7-90 (1/2" IRON), AZ. 341-42-17, 324.53'

Signed by David R. Lohr  
 Surveyor's Michigan License No. 30090

Date Sept. 19, 1996

