

SURVEY &
REMONUMENTATION

SEP 07 1999

SECTION

LAND CORNER RECORDATION CERTIFICATE

Filing Requirement of Act 74, Mich. P.A. 1970

Gladwin County Remonumentation

LIBER 001 PAGE 268

For Corners in
GLADWIN

(County)

Located In:

Corner Code#:

1. Public Land Survey T. 17N R. 2W E-5
T. R.
T. R.
2. Public Controlling S. T. R.
in Section S. T. R.
3. Miscellaneous S. T. R.
Property in Section S. T. R.
4. Lot No. , Recorded Plat
5. Private Claims

STATE OF MICHIGAN
GLADWIN COUNTY
Filed-Remon

16 AUG 1999 2:35:31 PM

BONNIE K. HOUSE
REGISTER OF DEEDS

Register of Deeds Stamp & File Number

I, Mark R. Robison, in a field survey on May 6, 1999, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law, established, re-established, monumented, re-monumented, recovered, found as expressed below.

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

1850 William A. Burt
Set Post Cor. Sec's 8, 9, 16 & 17
Wit-(1)Hemlock 14 S72E 20
(2)Do 8 N26W 19

1972 Lapham field notes &
witnesses

Wit-(6)Cor Post North 33.70'
(7)N61W T. Pole 59.15'
(8)S44W T. Pole 80.23'

1977 Lapham survey & wkg dwg
Wit-same as (6), (7) & (8)

1951 McCartney county road plans
1/2" Steel Rail
Wit-(3)N40E 75.5 8" Bloch ?
(4)N15W 62.00 12" Ash
(5)S35W 80.75 P.P.

1976 Fluharty LCRC#138
Fd 1/2" Bar

Wit-(9)P.P., S33W, 80.24'
(10)P.P., N60W, 59.12'
(11)Cor. Fe. Post, North, 33.72'

1987 Lapham survey
Wit-same as (6), (7) & (8)

1994 Lapham working dwg
Wit-none

B. Description of corner evidence found and/or method applied in restoring or re-establishing corner:

Found 1/2" x 8" rerod over P.K. Nail in centerline of road, opposite fence to North. Agrees with witnesses (4), (5), (7) & (10). Also agrees with County Road Plans (1951) and Lapham (1972) & (1974) measurements to D-5 & F-5. Replaced found 1/2" rerod with 5/8" rerod.

See dossier for detailed report.

APPROVED LAND CORNER

P.A. 345 of 1990
Gladwin County

Co. Rep. Mark R. Robison


Date 8/13/99

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

E-5: Set 5/8" x 36" rerod with Gladwin County Remonumentation cap marked P.S.#27458 in Monument Box.

Witnesses:

S45°W Power Pole, nail & tag, 80.15'
N60°W Power Pole, spike & cap, 59.05'
N15°W 24" Ash, nail & tag, 61.80'
South 5" Ash, nail & tag, 53.90'
N45°E 5" W. Pine, nail & tag, 55.00'



Signed by Mark R. Robison

Surveyor's Michigan License No. 27458

FORM APPROVED BY MICHIGAN STATE BOARD OF LAND SURVEYORS, JAN. 28, 1971
REVISED MAY 14, 1975
REVISED JAN., 1983
REVISED OCT., 1995