



Liber: **C1** Page: **872**

STATE OF MICHIGAN - GLADWIN COUNTY
RECORDED



Ann Manning - REGISTER OF DEEDS
11/30/2016 1:38 PM

Receipt #: 104426 Page: 1 of 2
30.00 CORNER

Land Corner Recordation Certificate
Authority: 1970 PA 74, MCL 54.205

Surveyor's Name: Joshua R. Davidson Field Survey Date: February 3, 2014
For corner(s) in: Gladwin County

Original Public Land Survey Corner			Corner Code
S _____	T _____	R _____	_____
S _____	T _____	R _____	_____
S _____	T _____	R _____	_____
S _____	T _____	R _____	_____

Property Controlling Corner			Corner Code
S _____	T _____	R _____	_____
S _____	T _____	R _____	_____
S _____	T _____	R _____	_____
S _____	T _____	R _____	_____

Property Corner				Corner Code
S _____	1	T 19N	R 01W	2
S _____	1	T 19N	R 01W	6
S _____		T _____	R _____	_____
S _____		T _____	R _____	_____

Protracted Public Land Survey Corner			Corner Code
S _____	T _____	R _____	_____
S _____	T _____	R _____	_____
S _____	T _____	R _____	_____
S _____	T _____	R _____	_____

	A	B	C	D	E	F	G	H	I	J	K	L	M	
1														1
2		6		5		4		3		2		1		2
3														3
4		7		8		9		10		11		12		4
5														5
6		18		17		16		15		14		13		6
7														7
8		19		20		21		22		23		24		8
9														9
10		30		29		28		27		26		25		10
11														11
12		31		32		33		34		35		36		12
13														13
	A	B	C	D	E	F	G	H	I	J	K	L	M	

Part A: Corner History

<u>2</u> – E 1/16 corner section 1	<u>6</u> – NE 1/16 corner section 1
– None	– None

Part B: Surveyor's Report on Perpetuation, Restoration, Reestablishment, or Monumentation of Corner

2 – E 1/16 corner section 1

Set stamped 2" aluminum cap on 5/8" X 34" rebar midway between closing corners on standard line.

6 – NE 1/16 corner section 1

Set stamped 2" aluminum cap on 5/8" X 34" rebar per BLM standard procedure.

Part C: Field Evidence of Perpetuation or Monumentation of Corner

2 – E 1/16 corner section 1

a stamped 2" aluminum cap on 5/8" x 34" rebar

N66°E 13.19' to set nail & tag in N. side 18" R. Maple
S04°W 33.81' to set nail & tag in W. side 10" Oak
S87°W 17.32' to set nail & tag in S. side 7" & 9" R. Maple
N19°W 25.22' to set nail & tag in E. side 12" R. Maple


Set blue post with location tag 1' Southwest

6 – NE 1/16 corner section 1

a stamped 2" aluminum cap on 5/8" X 34" rebar

S06°E 25.60' to set nail & tag in E. side 3" R. Pine
S69°W 44.56' to set nail & tag in S. side 3" R. Pine
N64°W 54.93' to set nail & tag in S. side 7" W. Pine
N02°W 15.45' to set nail & tag in E. side 4" Aspen

Set blue post with location tag 1' Southwest


Certifying Surveyor's Name

Professional Surveyor's License No.: 46659

Prepared By: Joshua R. Davidson
Department of Natural Resources
8015 Mackinaw Trail
Cadillac, MI 49601

November 28, 2016

Date

