

MAR 02 2000

SECTION

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

For corners in

Gogebic
(County)

Located In:

Corner Code ##

1. Public Land Survey

T 46N R 43W

I-9

T _____ R _____

T _____ R _____

T _____ R _____

2. Property Controlling
in Section

S _____ T _____ R _____

S _____ T _____ R _____

3. Miscellaneous
Property in Sec.

S _____ T _____ R _____

S _____ T _____ R _____

4. Lot No. _____, Recorded Plat _____

5. Private Claims _____

Section Corner 22, 23, 26 & 27; T.46 N., R.43 W.

I, Richard L. Drahn in a field survey on April 23, 19 99, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

Corner established by Austin Burt on 9/4/1851. Original B.T.s --- Hemlock 22" S.61 W. 15 links (9.90') --- Cedar 12" N.45 E. 11 links (7.26') ---

Corner position restored by Richard L. Drahn, RLS 21564 on 9/27/1984 from the remains of the original B.T.s and from line trees and natural features N, S, E & W. He set a 3/4" X4' aluminum rod with a 3 1/4" stamped aluminum cap and the following new B.T.s: ---9" Hemlock N.88 W. 25.57' --- 12" Hemlock S.26 E. 18.23' --- a triangular shaped boulder 4'X 4'X 4' with a chiselled "X" on top N.19 W. 30.09' --- 6' Steel sign rail N.50 W. 2.2' ---

Corner recorded in Gogebic County Liber 2, Page 651 on 12/10/84.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

Recovered the monument as described and the bearing trees as follows:

| | | | |
|-----|-----------------|---------|-------------------|
| 10" | Hemlock | N.87 W. | 25.33' (new nail) |
| 14" | Hemlock | S.25 E. | 18.31' (new nail) |
| "X" | Bolder | N.20 W. | 30.10' |
| 6' | Steel sign rail | N.52 W. | 2.07 |

Only stump holes remain from the original bearing trees.


Corner research on file with Gogebic County records.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

New bearing tree referenced:

12" Cedar N.69 E. 38.54'

Richard L. Drahn 5/11/99
COUNTY _____



Signed by Richard L. Drahn

Date April 29, 1999

Surveyor's Michigan License No. 21564

USFS R_17

FORM APPROVED BY MICHIGAN STATE BOARD OF LAND SURVEYORS, JAN. 28, 1971
REVISED MAY 14, 1975
REVISED JAN., 1983