

LAND CORNER RECORDATION CERTIFICATE

FILING REQUIREMENT OF ACT 74, MICH. P.A. 1970

FOR CORNERS OF—	LOCATED IN—	CORNER CODE NUMBER
1. PUBLIC LAND SURVEY	T. 25 N. R. 10 W.	J-10;
2. PROPERTY CONTROLLING IN SECTION 26	T. 25 N. R. 10 W.	12;
3. MISCELLANEOUS PROPERTY IN SECTION	T. S. R. W.	
4. LOT NO. ———, RECORDED PLAT. ———		
5. PRIVATE CLAIMS ———		

REGISTER OF DEEDS STAMP AND FILING NUMBER

I, CARL F. ROSER, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were, in a field survey on OCTOBER 12, 1983, established, re-established, monumented, re-monumented, recovered or restored as expressed below and in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a court of law. Furthermore, that the corner points mentioned in lines 3, 4 and 5 above were, in a field survey on _____, 19____, found, recovered, restored, established or re-established as expressed below and in conformance with the rules of the Michigan State Board of Registration for Land Surveyors or, by a Decree of a Court of law:

A. Description of original monument and accessories and/or subsequent restoration:

- B. Description of corner evidence found and/or method applied in restoring or re-establishing corner:
- J-10 - ESTABLISH CTR. OF SEC. 26 AT INTERSECTION OF ONE-QUARTER LINES. OLD FN (MOSTLY DOWN) TO WEST IS 1'± N. WINDING B. WIRE IN TREES TO SOUTH IS 10'± W.
- 12 - ESTABLISH SE COR. OF N 1/2 OF SW 1/4 OF SEC. 26, PER STD B.L.M. INSTRUCTIONS. CORNER FALLS IN OLD B-W & W-W EAST-WEST FENCE & 3'± E OF W-W FN TO N & B-W FN TO S. (FN'S MOSTLY DOWN OR IN TREES).

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

J-10			12		
DROVE 1" X 36" PIPE W/RLS CAP			DROVE 5/8" X 36" RE-ROD W/RLS CAP &		
& SET CED POST W/LOC TAG.			SET CEDAR POST W/LOC TAG.		
12" MAPLE	N50°E	34.1'	8" CEDAR	N54°W	8.0'
6" MAPLE	S65°E	37.2'	9" CEDAR	S20°E	8.4'
11" MAPLE	S24°W	27.5'	9" CEDAR	S36°W	22.3'
			CTR OF 5' CREEK SOUTH 45' ±		

SIGNED BY Carl F. Roser 6/07/84 DATE

SURVEYOR'S MICHIGAN REGISTRATION NO. 12028


FOR STATE AND UNITED STATES AGENCIES:

SIGNED BY _____ DATE _____

(CHIEF OF SURVEY PARTY)

APPROVED AND SIGNED BY _____ DATE _____

MICHIGAN REGISTERED LAND SURVEYOR



(SEAL)

SURVEYOR'S MICHIGAN REGISTRATION NO. _____ GRAND TRAVERSE COUNTY

FORM APPROVED BY MICHIGAN STATE BOARD OF REGISTRATION, JAN. 26, 1971
REVISED MAY 14, 1975

MAY PLACE SKETCH ON BACK OR ATTACHED SHEET