

LAND CORNER RECORDATION CERTIFICATE

FILING REQUIREMENT OF ACT 74, MICH. P.A. 1970

FOR CORNERS OF --:	LOCATED IN --:	CORNER CODE NUMBER
1. PUBLIC LAND SURVEY	T. 26 N. R. 11 W.	L-7;
2. PROPERTY CONTROLL- 13 ING IN SECTION	T. 26 N. R. 11 W.	16
3. MISCELLANEOUS PROPERTY IN SECTION	T. N. R. E. W.	
4. LOT NO. _____, RECORDED PLAT _____		
5. PRIVATE CLAIMS _____		

REGISTER OF DEEDS STAMP AND
FILING NUMBER

I, CARL F. ROSER, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were, in a field survey on JANUARY 31, 1983, established, re-established, monumented, re-monumented, recovered or restored as expressed below and in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a court of law. Furthermore, that the corner points mentioned in lines 3, 4 and 5 above were, in a field survey on _____, 19____, found, recovered, restored, established or re-established as expressed below and in conformance with the rules of the Michigan State Board of Registration for Land Surveyors or, by a Decree of a Court of law:

A. Description of original monument and accessories and/or subsequent restoration:

B. Description of corner evidence found and/or method applied in restoring or re-establishing corner:

- L-7 RE-ESTAB 1/4 COR TO SEC'S 13 & 24 EQUIDISTANT & ON LINE BETWEEN SEC COR'S TO E & W. FN REMAINS E-W-N (COULD NOT FIND COR FN POST) ARE ABOUT 6'±S & 1'±W. E.P. WATERMAN, 1917, INDICATES HE HAD 1/4 POST FROM U.S. B.T.'S, HEMLOCKS. COR FALLS ON STEEP HILL SIDE. JAXON CREEK IS SOUTH, 155'±, (N. EDGE OF STREAM).
- 16 - ESTABLISHED EAST 1/8 COR ON SOUTH SIDE OF SEC 13 MID-WAY & ON LINE BETWEEN SEC COR TO E & 1/4 COR TO W. AN OLD COR FN POST (B-W ON POST E & W & IN TREES, TO N. - CROOKED) IS NORTH 7'.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

L-7			16		
SET DNR MON & CEDAR POST			DROVE 5/8" X 34" REROD & SET CEDAR		
3" OAK	N16°E	33.1	POST W/LOC TAG		
4" W. PINE	N74°W	67.0	11" MAPLE	N10°W	8.2
5" MAPLE	N88°W	37.5	14" MAPLE	N80°E	27.2
E-W RANDOM	SOUTH	1.51	5" MAPLE	S20°E	20.7
			E-W RANDOM	SOUTH	2.02

SIGNED BY Carl F. Roser 06/02/83 DATE _____

SURVEYOR'S MICHIGAN REGISTRATION NO. 12028


FOR STATE AND UNITED STATES AGENCIES:

SIGNED BY _____ DATE _____

CHIEF OF SURVEY PARTY

APPROVED AND SIGNED BY _____ DATE _____

MICHIGAN REGISTERED LAND SURVEYOR



(SEAL)

SURVEYOR'S MICHIGAN REGISTRATION NO. _____ BLAIR TWP.
GRAND TRAVERSE COUNTY