

MICHIGAN
DEPARTMENT OF CONSERVATION
FORESTRY DIVISION

LAND CORNER RECORD

T. 27 N.R. 9 W
T. 26 N.R. 9 W


GRAND TRAVERSE COUNTY

DESCRIPTION OF CORNER SEC. CORNER COMMON TO SECTIONS 32 & 33 and 4 & 5.

CORNER MONUMENT FOUND 3/4" PIPE, SCHAAF PIPE AND OLE PINE STUMP. SET STD. DEPT. MON.
BELOW SURFACE

DATE MONUMENT PLACED AND WITNESSED JULY 1968

WITNESSES TO CORNER.....



12" Oak	S 87 W	44.7'
24" Oak	N 54 E	48.4'
36" Triple Oaks	S 24 E	73.4'

AND

Trail Road N & E from Corner

DESCRIPTION IN DETAIL AS TO HOW CORNER WAS LOCATED AND IDENTIFIED OR RESTORED.

This corner is a perpetuation of the Government corner that was perpetuated by Carver in 1927. His survey is on record at the County Court House. He located the corner from all four USBTs, of which the Y. Pine Stump to the SE is still standing. He set a pine stake, which we recovered, and which also checks his witnesses; B. Oak NE and Triple B. Oak SE.

SURVEYOR'S SEAL

SIGNED

Paul F. Roer

DATE

Sept. 16, 1968

REGISTERED LAND SURVEYOR

#12028