

LAND CORNER RECORDATION CERTIFICATE

FILING REQUIREMENT OF ACT 74, MICH. P.A.1970

FOR CORNERS OF:-	LOCATED IN:-	CORNER CODE NUMBER
1. PUBLIC LAND SURVEY	T 27 N. 9 W.	M-1
2. PROPERTY CONTROLLING IN SECTION- 1	T 27 N. 9 W.	5, 16, 9
3. MISCELLANEOUS PROPERTY IN SECTION-	T S. R. E. W.	
4. LOT NO. RECORDED PLAT-		
5. PRIVATE CLAIMS		

REGISTER OF DEEDS STAMP AND FILING NUMBER

I, **Carl F. Roser**, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were, in a field survey on **December 9**, 1981, established, re-established, monumented, re-monumented, recovered or restored as expressed below and in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a court of law. Furthermore, that the corner points mentioned in lines 3, 4 and 5 above were, in a field survey on , 19 , found, recovered, restored, established or re-established as expressed below and in conformance with the rules of the Michigan State Board of Registration for Land Surveyors or, by a Decree of a Court of law:

XX

B. Continued: fits M.S.H.D. Wits. dated March 1964.

C. Continued:

M-1

Fd. 3/4" pipe inside 1" pipe (buried)

*18" W. Pine S30°W 43.12

*16" Cherry (triple) N65°W 65.63

*Ced. fn. post S35°E 28.07

*=Old Wits.

B. Description of corner evidence found and/or method applied in restoring or re-establishing corner:

5 Accepted 20" live white pine tree for 1/8 cor. Gourdie-Fraser had computed position somewhere at this 20" W. Pine and E.P. Waterman in 1909 calls for "Stake by Pine Tree 5N75°E 2' on E. Side of wagon track".

16 Fd. & accepted 2 1/2 " angle iron in conc. for E1/8 cor. on South line of Sec. 1. Fits E. P. Waterman survey of Sec. 1 dated Aug. 1909.

9 Fd. & accepted old round conc. mon. for E1/8 cor. on E-W 1/4 line of Sec. 1. Old fence, mostly down to S & winding fn. in trees to W. Mon. fits E.P. Waterman sur. of Sec. 1 dated Aug. 1909.

M-1 Fd. 3/4" pipe inside 1" pipe for NE cor. of Sec. 1 (4 Twp. Cor) that fits prior survey & Wits by Gourdie-Fraser & old sur. of Sec. 1 by E.P. Waterman dated Aug. 1909. Cor. also

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

5	16	9
Fd. 20" W. Pine tree for 1/8 cor.	Fd. 2 1/2" angle ir. w/conc base, added ced. post w/loc. tag.	Fd. Rd. conc. mon. & added ced. post w/loc tag
Scribed 1/8 on East and South side of tree	20" Oak S50°W 13.6	12" Oak N70°W 13.3
Ctr. N-S trail West 8±	5" Maple (twin) S45°E 11.1	12" Oak N70°E 8.3
	8" Maple N20°E 32.5	9" Maple S45°W 13.1
	Old Cor. fence post, fn's N & W mostly down, is 1' West of angle iron.	

SIGNED BY

Carl F. Roser 01-21-82

DATE

SURVEYOR'S MICHIGAN REGISTRATION NO. 12028

FOR STATE AND UNITED STATES AGENCIES:

SIGNED BY


CHIEF OF SURVEY PARTY

DATE

APPROVED AND SIGNED BY

MICHIGAN REGISTERED LAND SURVEYOR

DATE



(SEAL)

SURVEYOR'S MICHIGAN REGISTRATION NO.

GRAND TRAVERSE COUNTY