

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970 as Amended

For corners in

Houghton (County)	Located In:	Corner Code #
1. Public Land Survey	T R	
	T R	
	T R	
2. Property Controlling in Section	S 29 T 52N R 35W	16
	S 33 T 52N R 35W	3
	S T R	
3. Miscellaneous Property in Sec.	S T R	
	S T R	
4. Lot No. , Recorded Plat		
5. Private Claims		

Register of Deeds Stamp & File Number

	A	B	C	D	E	F	G	H	I	J	K	L	M
1													
2	6		5		4		3		2		1		
3													
4	7		8		9		10		11		12		
5													
6	18		17		16		15		14		13		
7													
8	19		20		21		22		23		24		
9													
10	30		29		28		27		26		25		
11													
12	31		32		33		34		35		36		
13													

I, Stephan J. Szyszkoski, in a field survey on 3 01/17/2012 do hereby state
that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2
above were in conformance with regulations and rules therefore as required in the current manual of survey
instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of
a Court of Law and /or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with
the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established,
re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded
on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

(16-Sec. 29) East 1/16 corner between Sections 29 and 32. Not previously monumented.

(3-Sec. 33) North 1/16 corner between Sections 32 and 33. Not previously monumented.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

(16-Sec. 29) Established the position for the corner midway and on the Section line between Quarter
corner 1305.10' west and Section corner 1305.10' east.

(3-Sec. 33) Established the position for the corner midway and on the Section line between Section
corner 1326.46' north and Quarter corner 1326.46' south.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:


(16) Set 1"IDx32" I.pipe with 4" alum. MDNR cap.
Set measuring nail with MDNR tag in the side of:
10" Maple S20W 23.7' mrkd "1/16S BT"
10" twin Y.Birch S83W 5.1' do
4" Y.Birch S72E 18.5' do
3" Y.Birch S49E 2.0' do
Set sq'd Cedar post adjacent.
Bearings are magnetic.

(3) Set 1"IDx32" I.pipe with 4" alum. MDNR cap.
Set measuring nail with MDNR tag in the side of:
9" Maple N13E 11.6' mrkd "1/16S BT"
5" Maple N70E 13.45' do
10" Sugar S46E 6.65' do
6" Sugar N08W 8.35' do
Set sq'd Cedar post adjacent.
Bearings are magnetic.

Signed by Stephan J. Szyszkoski
Surveyor's Michigan License No. 33986

Date 01/31/2012

For the Michigan Department of Natural Resources, Forest Resources Division



16816

16817