

LAND CORNER RECORDATION CERTIFICATE  
Filing Requirement of Act 74, Mich. P.A. 1970 as Amended

For corners in

Houghton (County)	Located In:	Corner Code #
1. Public Land Survey	T 52N R 35W	E9
	T R	
	T R	
2. Property Controlling in Section	S 29 T 52N R 35W	2
	S T R	
3. Miscellaneous Property in Sec.	S T R	
	S T R	
4. Lot No. _____, Recorded Plat		
5. Private Claims		

Register of Deeds Stamp & File Number

	A	B	C	D	E	F	G	H	I	J	K	L	M
1													
2		6		5		4		3		2		1	
3													
4		7		8		9		10		11		12	
5													
6		18		17		16		15		14		13	
7													
8		19		20		21		22		23		24	
9													
10		30		29		28		27		26		25	
11													
12		31		32		33		34		35		36	
13													

I, Stephan J. Szyszkoski, in a field survey on 03/28/2012 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and /or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

(E9) Corner common to Sections 20-21-28-29. 1953 - Corner position reestablished by D.C.DeLaMater RLS by double proportionate measurement to the original record. Set 1" pipe with 4" brass cap. 10" H.Maple S70E 14 links, 14" H.Maple S40W 48 links. 1995 - The 1953 monument was recovered by MDNR forester Otto Jacob. Mr. Jacob blazed and scribed 4 adjacent trees facing the monument.

(2-Sec. 29) East 1/16 corner between Sections 20 and 29. Not previously monumented.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

(E9) The 1953 monument was recovered in good condition. The 1953 witnesses were not found. Found 4 nearby trees with overgrown or partially overgrown blazes facing the corner monument, presumably those marked in 1995. These trees were used as witnesses as described below. Accepted the monument as a careful and faithful reestablishment of the position of the original corner.

(2-Sec. 29) Established the position for the corner midway and on the Section line between Quarter corner 1349.17' west and Section corner 1349.17' east.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

(E9) Found 1"ID I.pipe with 4" brass MI Dept. of Conservation cap.  
Set measuring nail with MDNR tag in the side of:  
12" Y.Birch N33W 22.35' overgrown blazes  
8" Sugar N59E 13.6' do  
9" Sugar S32E 29.4' old blaze and scribing  
6" Sugar S69W 39.5' do  
Set sq'd cedar post adjacent.  
Bearings are magnetic.

(2) Set 1"IDx32" I.pipe with 4" alum. MDNR cap.  
Set measuring nail with MDNR tag in the side of:  
6" Sugar N27W 16.25' mrkd "1/16S BT"  
8" Sugar N86E 10.6' do  
9" Sugar S12E 35.6' do  
14" Sugar S72W 30.25' do  
Set sq'd cedar post adjacent.  
Bearings are magnetic.

Signed by Stephan J. Szyszkoski  
Surveyor's Michigan License No. 33986

Date 04/05/2012

For the Michigan Department of Natural Resources, Forest Resources Division

