

Robert W. Crampton
9/24/99

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

RECORDED

JAN 25 2000

SECTION

For corners in
HOUGHTON
(County)

Located In:

Corner Code #

MARY SCHDOES 09/27/99
HOUGHTON COUNTY, REGISTER 10:11
LC 4/ 31 PAU Fee: 9.00
Page 1 of 1

1. Public Land Survey

T 53N R32W 6 (B/C-7)
T 53N R32W #7 8 (A-7/8) ✓
T R
T R

2. Property Controlling
in Section

S T R
S T R

3. Miscellaneous

S T R

Property in Section

S T R

Changed per
County Rep
on 2/7-00 to
7

Register of Deeds Stamp & File Number

4. Lot No. _____, Recorded Plat _____

5. Private Claims _____

	A	B	C	D	E	F	G	H	I	J	K	L	M
2	6		5		4		3		2				
3													
4	7		8		9		10		11		12		
5													
6	18		17		16		15		14		13		
7													
8	19		20		21		22		23		24		
9													
10	30		29		28		27		26		25		
11													
12	31		32		33		34		35		36		
13													

I, R.W. CRAMPTON, in a field survey on APRIL 27, 19 99,
do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned
in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current
manual of survey instructions of the United States Department of the Interior, Bureau of Land
Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and
5 above were in conformance with the rules of the Michigan Board of Professional Surveyors or by a
Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found
as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded
on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

6. HEMLOCK 10 FOR MEANDER CORNER, CEDAR 8 N5W 10.

8. SET MEANDER POST, TAMARACK 4 N54W 16, TAMARACK 3 N22E 31.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:


6. FOUND 1/2" IRON PIPE WITH CONCRETE IN VCP, FROM THE PLAT OF THE VILLAGE OF JACOBSVILLE
(CABINET 1, FOLIO 73).

8. FOUND 4" CONCRETE MONUMENT WITH 1/2" ROD AND CAP WITH NO. 15408 (EWART MULLER)
EXCEPTED AS CORNER..

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

6. THE 1/2" IRON PIPE WAS WITNESSED WITH SURVEY TAG NAILED TO:
10" Y. BIRCH TREE N18°W 63.53', 6" APPLE TREE S83°W 91.18',
N42°E 39.36' TO 1 1/4" IRON PIPE, N65°W 98.40' TO NE COR. HOUSE.

8. THE 4" CONCRETE MONUMENT WAS WITNESSED WITH SURVEY TAG NAILED TO:
6" TWIN W. BIRCH TREE N45°W 2.99', 8" W. BIRCH TREE S59°E 10.32',
4" TWIN SPRUCE TREE S14°E 6.00', 4" TWIN W. BIRCH TREE S65°W 8.78'.



Signed by Robert W. Crampton

Date SEPT. 9, 1999

Surveyor's Michigan License No. 24591