

APPROVED LAND CORNER  
P.A. 345 OF 1990  
Houghton County

APR 30, 1999  
*Robert W. Campbell*

SURVEY &  
REMONUMENTATION

JUL 23 1999

SECTION

LAND CORNER RECORDATION CERTIFICATE  
Filing Requirement of Act 74,  
Mich. P.A. 1970

For corners in

Houghton County  
(County)

Located In:

Corner Code #

MARY SCHDOOS 05/05/99 2  
HOUGHTON COUNTY, REGISTER 15:04  
LC 3/ 589 PAU Fee: 9.00  
Page 1 of 1

1. Public Land Survey Section 7 T 54N R 32W A, B-3 #3  
T R (Meander Corner)  
T R  
T R  
T R
2. Property Controlling S T R  
in Section S T R
3. Miscellaneous S T R  
Property in Sec. S T R
4. Lot No. , Recorded Plat
5. Private Claims

Register of Deeds Stamp & File  
Number

Corner A, B-3 is the meander corner on the E. shore of Portage Lake, on section line common to Section 6 & 7, T54N, R32W.

I, Michael T. Drewyor, in a field survey on December 23, 19 97 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and /or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

Meander Corner - At 47.24 chains (from the NE corner Section 7), intersect north arm of Portage Lake.

Set Meander Corner - Spruce 8  
Spruce 6, S65E, 04

No evidence of original monument or accessories found. This line was originally surveyed by Deputy Surveyor William Ives between July 5, 1845 and July 13, 1845.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

Meander Corner - In September 1955, Helmuth M. Steinhilb, RLS 8896 shows on a map that he set this meander corner. Upon retracing Helmuth's survey I did not find any iron pipe along the shore of Portage Lake on the section line. This meander corner was restored with information on the 1955 survey by Helmuth, using the found north quarter corner to the east and the evidence found in the field.


C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

All witness points in trees are PK nails and washers.

Meander Corner - Set 1/2" iron.

Witnesses:

N 58° E, 30.09 ft., NW Building Corner Frame Cabin  
S 22° E, 55.63 ft., 16" Maple  
S 23° W, 28.05 ft., 7" Spruce  
S 60° W, 28.12 ft., 8" Maple



Signed by *Michael T. Drewyor* Date April 13, 1999

Surveyor's Michigan License No. 24245

FORM APPROVED BY MICHIGAN STATE BOARD OF PROFESSIONAL SURVEYORS, JAN. 28, 1971

REVISED MAY 14, 1975  
REVISED JAN., 1983  
REVISED OCT., 1995

By: Hitch, Inc., P.C., Houghton, MI  
Job No. 97012