

LAND CORNER RECORDATION CERTIFICATE  
Filing Requirement of Act 74, Mich. P.A. 1970 as Amended

For corners in

Houghton (County)	Located In:	Corner Code #
1. Public Land Survey	T 55N R 32W	B9
	T R	
	T R	
2. Property Controlling in Section	S T R	
	S T R	
	S T R	
3. Miscellaneous Property in Sec.	S T R	
	S T R	
4. Lot No. , Recorded Plat		
5. Private Claims		

Register of Deeds Stamp & File Number

	A	B	C	D	E	F	G	H	I	J	K	L	M
1													
2	6		5		4		3		2		1		
3													
4	7		8		9		10		11		12		
5													
6	18		17		16		15		14		13		
7													
8	19		20		21		22		23		24		
9													
10	30		29		28		27		26		25		
11													
12	31		32		33		34		35		36		
13													

I, Stephan J. Szyszkoski, in a field survey on 07/25/2011 do hereby state  
that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2  
above were in conformance with regulations and rules therefore as required in the current manual of survey  
instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of  
a Court of Law and /or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with  
the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established,  
re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded  
on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

(B9) Quarter corner common to Sections 19 and 30. 1845 - Established by D.Houghton Deputy Surveyor  
40.00 chains east of Section corner A9. Set post. Cedar 9" S52W 13 links, Spruce 7" N34E 15 links.  
2011 - Steven C. Hein PS 32336 reports that he recovered a 1.5" ID iron pipe (date not known by  
undersigned) in accord with witnesses made by M.C.Larsen, and made new witnesses (nail and tag):  
Cedar N63W 21.84', Cedar S43E 11.54', Cedar S37W 10.42', Cedar N03W 24.04'. The last two noted were  
also the M.C.Larsen witness trees.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

(B9) Found a 1.5"ID iron pipe with flattened top leaning over to the east, in an old winter road,  
apparently having been disturbed by wheeled vehicles. Reset the pipe at record bearing and distance  
from three of Mr. Hein's witnesses, described below. Mr. Hein's witness Cedar N03W is down. The  
pipe is S88 deg. 00'10"E 2666.67' from Section corner A9 (true bearing). Accepted the pipe as the  
best available evidence of the position of the original corner.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

(B9) Reset 1.5"ID Iron pipe projecting 17" a.g.  
Fd. measuring nail with tag 32336 in:  
5" Cedar N63W 21.84' w/overgrown blazes  
6" Cedar S43E 11.54' do  
7" Cedar S37W 10.42' do  
Set measuring nail with MDNR tag in the side of:  
7" W.Birch North 11.44' mrkd "1/4S NBT"  
Set sq'd cedar post adjacent.  
Bearings are magnetic.



Signed by Stephan J. Szyszkoski Date 11/17/2011  
Surveyor's Michigan License No. 33986

For the Michigan Department of Natural Resources, Forest Management Division