

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970 as Amended

For corners in

Houghton (County)	Located In:	Corner Code #
1. Public Land Survey	T R	
	T R	
	T R	
2. Property Controlling in Section	S 13 T 55N R 33W	4
	S T R	
	S T R	
3. Miscellaneous Property in Sec.	S T R	
	S T R	
4. Lot No. , Recorded Plat		
5. Private Claims		

Register of Deeds Stamp & File Number

	A	B	C	D	E	F	G	H	I	J	K	L	M
1													
2	6		5		4		3		2		1		
3													
4	7		6		5		4		3		2		1
5													
6	18		17		16		15		14		13		
7													
8	19		20		21		22		23		24		
9													
10	30		29		28		27		26		25		
11													
12	31		32		33		34		35		36		
13													

I, Stephan J. Szyszkoski, in a field survey on 08/01/2011 do hereby state
that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2
above were in conformance with regulations and rules therefore as required in the current manual of survey
instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of
a Court of Law and /or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with
the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established,
re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded
on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

(4-Sec. 13) Northwest 1/16 corner, Section 13. Not established in the original survey. This corner
falls within Lot 1 of Block 21 of the recorded plat of Tamarac City, Mich., dated 1885, and is shown
on that plat as "1/16 post". Found no subsequent record. R.W.Crampton PS #24591 reports finding a
bent 2"ID iron pipe, apparently located on the North 1/16 line of Section 13, west of the position
for the 1/16 corner, possibly being a plat corner on the north line of Outlot A of said plat, but not
known to be so. Mr. Crampton replaced the pipe with a 1/2" iron pipe with plastic cap, west of the
position for the corner.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

(4-Sec. 13) No monumentation was recovered at the corner position. At 147.12' west of the position
subsequently monumented, recovered a 1/2"ID iron pipe with plastic cap #24591 - being that noted by
Mr. Crampton as marking the position of the 2" iron pipe that he found. The 1/2" iron pipe is bent
at the surface but the subsurface portion was recovered plumb. I accepted this pipe as a
perpetuation of the direction of the North 1/16 line of Section 13. I reestablished the position for
the NW1/16 corner at the intersection of straight lines between 1/16 corner #3, Sec. 13 and Mr.
Crampton's pipe, with the West 1/16 line of Section 13, it being parallel to the west Section line
(from K5 to 1/16 cor. #3) and passing through monumented 1/16 corner #1, Sec. 13. In addition to
monumenting 1/16 corner #4, I straightened and reset the Mr. Crampton's 1/2" iron pipe 147.12' west
of 1/16 #4.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

(4) Set 1"IDx32" I.pipe with 4" alum. MDNR cap.
Set measuring nail with MDNR tag in the side of:
12" Basswood N34W 7.05' no blazes or marks
6" Sugar S24W 16.0' do
Fd. capped iron in conc. N69E 12.05'
Fd. capped iron in conc. S58E 31.98'
The capped irons were set by R.Haataja PS39478
in 2001 in a survey for lot line adjustment
in lots 1,2,11,12 in Block 21 of the recorded
plat of Tamarac City, Mich.



Signed by Stephan J. Szyszkoski
Surveyor's Michigan License No. 33986

Date 11/15/2011

For the Michigan Department of Natural Resources, Forest Management Division