

# 1999 REMONUMENTATION

Re Mon Libw1, Page 263

## LAND CORNER RECORDATION CERTIFICATE Filing Requirement of Act 74, Mich. P.A. 1970

STATE OF MICHIGAN  
HURON COUNTY  
RECORDED

For corners in

Huron

(County)

Located In:

Corner Code #

28 OCT 99 9:18 A.M.

FRANCES L. HOLLWICK  
REGISTER OF DEEDS

1. Public Land Survey Gore T18N R15E D-13  
T R  
T R  
T R
2. Property Controlling in Section S T R  
S T R
3. Miscellaneous Property in Sec. S T R  
S T R

Register of Deeds Stamp & File Number

4. Lot No. , Recorded Plat
5. Private Claims

I, Charles S. Getz, in a field survey on April 14, 1999 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law, established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

	A	B	C	D	E	F	G	H	I	J	K	L	M
1													
2	6			5			4		3		2		1
3													
4	7			8			9		10		11		12
5													
6	18			17			16		15		14		13
7													
8	19			20			21		22		23		24
9													
10	30			29			28		27		26		25
11													
12	31			32			33		34		35		36
13													

### A. Description of original monument and accessories and/or subsequent restoration:

D-13 1834 G.L.O., H. Parke D.S. County Road Commission Records - Refers to Rubicon Corner  
Set quarter section post  
Cedar 10", N79½°W, 33 Links Recorded Surveys - NONE  
Black Beech 6", N84°E, 4 Links Unrecorded Surveys - NONE  
L.C.R.C. - NONE


County Surveyor Records -  
June 2nd AD 1865-Description  
refers to Corner

### B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

D-13  
S 1/4 Cor, Section 32, T18N-R15E  
Found no evidence of original corner position  
Re-established corner position by proportionate measure from G.L.O. Notes,  
between E-13 and C-13 as best evidence of original corner position for D-13  
(On Kinde Road)

### C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

D-13  
S 1/4 Cor, Section 32, T18N-R15E  
Set 1/2" Iron Bar in Monument Box (Capped)  
West 41.91' to Monument Box  
S05°E 37.00' to East End of Culvert  
S05°W 43.10' to West End of Culvert  
North 57.40' to Nail in Power Pole  
West 2646.79' to SW Cor, Sec 32, T18N-R15E



Signed by Charles S. Getz  
Surveyor's Michigan License No. 25843

Date August 21, 1999

PEER GROUP APPROVED AT MEETING  
HELD October 26, 1999. R.P.B.