

SURVEY &  
REMONUMENTATION

APR 27 1995

COMMISSION

IOSCO COUNTY REMONUMENTATION CORNER  
LAND CORNER RECORDATION CERTIFICATE  
Filing Requirement of Act 74, Mich. P.A. 1970

STATE OF MICHIGAN  
IOSCO COUNTY  
FILED

5 DEC 94 1:53 P.M.

BONITA N. COYLE  
REGISTER OF DEEDS

94-21

Register of Deeds Stamp & File Number

For corners in

Tosco  
(County)

Located In:

Corner Code #

1. Public Land Survey

T 22N R 8E

C-9 to C-10

T R

T R

T R

S T R

S T R

S T R

S T R

2. Property Controlling  
in Section

3. Miscellaneous  
Property in Sec.

4. Lot No. , Recorded Plat

5. Private Claims

I, James H. Granger, in a field survey on September, 19 94,  
do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned  
in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the  
current manual of survey instructions of the United States Department of the Interior, Bureau of Land  
Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5  
above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a  
Court of Law; established, re-established, monumented, re-monumented, recovered, found as  
expressed below:

**NOTE: Not more than 4 corners, all in the same town and range, may be recorded  
on this certificate.**

A. Description of original monument and accessories and/or subsequent restoration:

1843 Original Survey  
John Mullett

Set Wood Post  
12" Yellow-Pine N78°W 41 lks


B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

Field search located cor. C-9 and monuments on sec. line as shown on MDOT road  
plans. Extended sec. line south and meander cor. falls 70' into Lake Huron.

Set witness cor. 138.06' N. of cor. position on section line.

ACCEPTED BY THE IOSCO COUNTY  
SURVEY PEER GROUP AS THE  
OFFICIAL CORNER UNDER P.A.  
345 OF 1990 AT A MEETING  
HELD ON 11-10-94

James H. Granger



C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

Set 5/8" x 30" rebar with alum. cap as witness cor. to meander cor.

S50°W 35.80' Inscribed "x" on S.E. side of light pole  
N76°E 76.82' Set tag in Power Pole  
S60°E 43.94' N.W. cor. of green Sided Building (State Wide Real Estate)  
S 3.00' Set PK nail in asphalt sidewalk

Signed by James H. Granger

Date November 10, 1994

Surveyor's Michigan License No. 16041