

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970 as Amended

For corners in

Iron (County)	Located In:	Corner Code #
1. Public Land Survey	T R	
	T R	
	T R	
2. Property Controlling in Section	S 8 T 43N R 31W	1
	S 8 T 43N R 31W	8
	S T R	
3. Miscellaneous Property in Sec.	S T R	
	S T R	
4. Lot No. , Recorded Plat		
5. Private Claims		

Register of Deeds Stamp & File Number

	A	B	C	D	E	F	G	H	I	J	K	L	M
1													
2	6		5		4		3		2		1		
3													
4	7		8		9		10		11		12		
5													
6	18		17		16		15		14		13		
7													
8	19		20		21		22		23		24		
9													
10	30		29		28		27		26		25		
11													
12	31		32		33		34		35		36		
13													

I, Stephan J. Szyszkoski, in a field survey on 05/15/14 do hereby state
that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2
above were in conformance with regulations and rules therefore as required in the current manual of survey
instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of
a Court of Law and /or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with
the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established,
re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded
on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

(1-Sec. 8) West 1/16 corner between Sections 5 and 8. 1975 - Established by A.O. Enger RLS midway
and on line between Section corner 19.925 chains west and 1/4 corner (in pond) 19.925 chains east.
Set 1"IDx36" I.pipe with 3 3/4" alum. cap. Tamarack 4" S37°E 25.3', Tamarack 2" S59°W 50.4'.

(8-Sec. 8) Center West 1/16 corner, Section 8. Not previously monumented.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

(1-Sec. 8) Found the 1975 monument in good condition, substantially at the record position, 1314.62'
east of Section corner and 1315.28' west of Quarter corner position in pond, and at record bearing
and distance from the Tamarack BT S37°E 25.3', now a dead stub. The second Tamarack BT was not
recovered. Accepted the monument as a careful and faithful establishment of the position of the
corner.

(8-Sec. 8) Established the position for the corner midway and on a straight line between Quarter
corner 1316.03' west and the Center of Section 8 1316.03' east.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

(1) Found 1"ID I.pipe with 3 3/4" alum. MDNR cap.
Set measuring nail with MDNR tag in the side of:
3" Spruce S89°E 13.2' mrkd "1/16S BT"
6" Tamarack S08°E 25.6' do
6" W.Birch S23°W 7.2' do
4" B.Spruce N48°W 34.3' do
1" capped iron pipe on Sec. line East 200.01'
Set sq'd cedar post adjacent.
E= 7906026.206 N= 152115.506

(8) Set 1"IDx28" I.pipe with 4" alum. MDNR cap.
Set measuring nail with MDNR tag in the side of:
5" B.Ash N20°E 29.1' mrkd "1/16S BT"
11" Spruce S35°E 15.65' do
8" Spruce S43°W 3.7' do
7" Spruce N46°W 16.7' do
Set sq'd cedar post adjacent.
E= 7906009.919 N= 151302.247

Bearings are magnetic. Coordinates are MCS83 in meters (NAD83(2011) Datum)
Coord. Ref.=NGS PID RL0240: N= 145070.957 m. E= 7907633.634 m.

Signed by Stephan J. Szyszkoski
Surveyor's Michigan License No. 33986

Date 06/03/2014

For the Michigan Department of Natural Resources, Forest Resources Division

