

SURVEY &
REMONUMENTATION

JAN 19 1999

SECTION

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

For corners in

	Iron (County)	Located In:	Corner Code #
1. Public Land Survey		T <u>43N</u> R <u>33W</u>	<u>G-3</u>
		T <u> </u> R <u> </u>	<u> </u>
		T <u> </u> R <u> </u>	<u> </u>
		T <u> </u> R <u> </u>	<u> </u>
2. Property Controlling in Section	S <u> </u>	T <u> </u> R <u> </u>	<u> </u>
	S <u> </u>	T <u> </u> R <u> </u>	<u> </u>
3. Miscellaneous	S <u> </u>	T <u> </u> R <u> </u>	<u> </u>
Property in Sec.	S <u> </u>	T <u> </u> R <u> </u>	<u> </u>

IRON COUNTY
MICHIGAN
RECEIVED FOR RECORD

98 DEC 28 AM 11:27

L.C. Records: L. 7, P. 328

G. L. Pisoni

REGISTERED LAND SURVEYOR

Register of Deeds Stamp & File Number

4. Lot No. , Recorded Plat
5. Private Claims

Section Corner Sections 3, 4, 9, and 10, T43N, R33W

Gary L. Pisoni, in a field survey on March 30, 1998 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

VOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

	A	B	C	D	E	F	G	H	I	J	K	L	M
1													
2	6		5			4		3		2		1	
3							●						
4	7		8			9		10		11		12	
5													
6	18		17			16		15		14		13	
7													
8	19		20			21		22		23		24	
9													
10	30		29			28		27		26		25	
11													
12	31		32			33		34		35		36	
13													

A. Description of original monument and accessories and/or subsequent restoration:

Original corner established in September, 1851 by Guy H. Carleton, U.S. Deputy Surveyor.
Original Corner; Section Corner Post and Meander Corner Post
Original Bearing Trees:

White Pine	20"	N 05° E	49 lks (32.34 feet)
White Pine	18"	S 31° E	49 lks (32.34 feet)

On 7/19/73, Arthur O. Enger, RLS with Michigan Dept. of Natural Resources restored the corner position from the original bearing tree stumps, he set a 1" diameter by 36" long iron pipe with a 3 1/2" aluminum cap stamped as follows: DNR, T43N, R33W, S-3, S-4, S-9, S-10, 1973, RLS 13581; 6" above ground surface and recorded in L.C. Certificate, Liber 1, Page 445-446 on 9/17/76.

1973 Bearing Trees:

White Spruce	8"	S 42° E	6.4 feet
White Spruce	13"	N 47° E	23.2 feet

3. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

Found the above described original bearing tree stumps from which Arthur Enger set the Section corner. Said corner is 6 feet from river's edge.

Found monument as described above and the following bearing tree:

White Spruce	14"	N 49° E	23.58 feet
--------------	-----	---------	------------

I accept the above monument as the best available evidence for restoring the corner position.

Corner record research on file with County Representative.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

Blazed and scribed the following new bearing trees: (All measurements taken to a nail in side of tree)

White Spruce	15"	N 02° W	49.72 feet
White Spruce	15"	N 82° E	42.34 feet
White Spruce	15"	S 12° E	25.24 feet
Steel sign post		N 82° E	2.25 feet

98-89

Signed by

Gary L. Pisoni


Date

12-21-98

Surveyor's Michigan License No.

27457

FORM APPROVED BY MICHIGAN STATE BOARD OF PROFESSIONAL SURVEYORS, JAN. 24, 1971
No. 27457 REVISED MAY 14, 1975
REVISED JAN., 1993
REVISED OCT., 1995



L. 7 P. 328