

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

For corners in

Iron
(County)

Located In:

Corner Code #

1. Public Land Survey

T 43N R 35W

C-6

2. Property Controlling
in Section

S T R

3. Miscellaneous
Property in Sec.

S T R

4. Lot No. , Recorded Plat

5. Private Claims

Quarter Corner S-18, S-17, T43N, R35W

Gary L. Pisoni

October 19 94

I, Gary L. Pisoni, in a field survey on October 19, 1994, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

Original corner established by Harvey Mellen, U.S Deputy Surveyor in 1851.

Original corner: Wood Post

Original bearing trees:

Cedar 9"
Cedar 10"

S 85°W
S 79°E

4 links(2.64 feet)
22 links(14.52 feet)

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

No evidence of original corner or bearing tree remains. Corner position found marked by a 3/4" x 4" iron pipe and a 4"x4" wood post. Corner position has been used and accepted as the corner locally for many years.

The corner is accepted as the best available evidence of the position of the original corner.

County Record Research on file with County Representative office.

Placed iron pipe next to an aluminum pipe monument which is located 3" above ground surface as described below.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

At the corner position, I set a 2" diameter by 30" long split base aluminum pipe monument with a 3" cast aluminum cap, stamped to read: Iron County Remonumentation, T43N, R35W, 1/4, S-18, S-17, 1994, RLS- 27457 from which I established the following new blazed and scribed bearing trees: (all measurements taken to a nail in side of tree)

White Birch	8"	N 22°E	34.01 feet
Cedar	12"	S 83°E	39.76 feet
Cedar	14"	S 39°W	40.71 feet
Balsam	4"	N 54°W	18.10 feet
Steel Sign Post		North	1.05 feet

Signed by Gary L. Pisoni

Date 1-9-95

Surveyor's Michigan License No. 27457

REGISTER'S OFFICE) ..SS
IRON COUNTY, MICH.)
RECEIVED FOR RECORD THE 21ST DAY OF
FEBRUARY A.D. 19 95 AT
2:45 O'CLOCK P M., AND RECORDED IN LIBER
6 OF L.C. RECORDS
ON PAGE 368
Deputy REGISTER OF DEEDS


Register of Deeds Stamp & File Number

	A	B	C	D	E	F	G	H	I	J	K	L	M
2	6	5	4	3	2	1							
3													
4	7	8	9	10	11	12							
5													
6	18	17	16	15	14	13							
7													
8	19	20	21	22	23	24							
9													
10	30	29	28	27	26	25							
11													
12	31	32	33	34	35	36							
13													

PEER GROUP APPROVED

IRON Gary L. Pisoni

COUNTY REPRESENTATIVE



FORM APPROVED BY MICHIGAN STATE BOARD OF LAND SURVEYORS, JAN. 28, 1971
REVISED MAY 14, 1975
REVISED JAN., 1983

LIBER

6 PAGE 368