

# LAND CORNER RECORDATION CERTIFICATE

## FILING REQUIREMENT OF ACT 74, MICH. P.A.1970

IRON COUNTY

FOR CORNERS OF—	LOCATED IN—	CORNER CODE NUMBER
1. PUBLIC LAND SURVEY	T. <u>44</u> N. <u>X</u> , R. <u>32</u> W.	<u>B9, A9</u>
2. PROPERTY CONTROLLING IN SECTION	T. _____ N. _____ E. S. _____ R. _____ W.	_____
3. MISCELLANEOUS PROPERTY IN SECTION	T. _____ N. _____ E. S. _____ R. _____ W.	_____
4. LOT NO. _____, RECORDED PLAT _____		
5. PRIVATE CLAIMS _____		

REGISTER OF DEEDS STAMP AND FILING NUMBER

I, Keith L. Sackett, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were, in a field survey on 8-17, 1984, established, re-established, monumented, re-monumented, recovered or restored as expressed below and in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a court of law. Furthermore, that the corner points mentioned in lines 3, 4 and 5 above were, in a field survey on \_\_\_\_\_, 19\_\_\_\_, found, recovered, restored, established or re-established as expressed below and in conformance with the rules of the Michigan State Board of Registration for Land Surveyors or, by a Decree of a Court of law:

A. Description of original monument and accessories and/or subsequent restoration:

Corner B9: Original Monument and Accessories Not Found. Found 1" Iron Rod set by unknown person.

Corner A9: Original Monument and Accessories Not Found. Found 1½" Iron pipe by unknown length buried in old fence line. Appears to have been used as corner for many years.

B. Description of corner evidence found and/or method applied in restoring or re-establishing corner:

Corner B9: Restored at 1" iron rod. It fits good with other corners in area.

Corner A9: Restored at iron pipe. This pipe appears to be a little south in relation to other corners but was accepted because of its long use.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

Corner B9: 1" Iron Rod by unknown length.  
7" Balsam N44W 24.8 ft. ¼S, NBT  
22" Pine N26E 27.3 ft. ¼S, NBT  
5" Maple S12E 13.7 ft. ¼S, NBT

Corner A9: 1½" Iron pipe by unknown length.  
6" Maple N31E 28.2 ft. S19, NBT  
8" Maple S45E 26.1 Ft. S30, NBT  
9" Y. Birch S66W 9.1 ft. S25, NBT

SIGNED BY \_\_\_\_\_ DATE \_\_\_\_\_

SURVEYOR'S MICHIGAN REGISTRATION NO. \_\_\_\_\_

(SEAL)

FOR STATE AND UNITED STATES AGENCIES:


SIGNED BY \_\_\_\_\_ DATE \_\_\_\_\_

APPROVED AND SIGNED BY Keith L. Sackett  
MICHIGAN REGISTERED LAND SURVEYOR

DATE 8-20

Keith L. Sackett  
Michigan Department of Natural Resources

SURVEYOR'S MICHIGAN REGISTRATION NO. 19006



FORM APPROVED BY MICHIGAN STATE BOARD OF REGISTRATION, JAN. 28, 1971  
REVISED MAY 14, 1978

MAY PLACE SKETCH ON BACK OR ATTACHED SHEET