

LAND CORNER RECORDATION CERTIFICATE  
Filing Requirement of Act 74, Mich. P.A. 1970 as Amended

For corners in

Iron (County)	Located In:	Corner Code #
1. Public Land Survey	T 45N R 31W	D9 (GCDB 240300)
2. Property Controlling in Section	S 29 T 45N R 31W	2 (GCDB 260300)
3. Miscellaneous Property in Sec.	S T R	
4. Lot No. , Recorded Plat		
5. Private Claims		

Register of Deeds Stamp & File Number

	A	B	C	D	E	F	G	H	I	J	K	L	M
1													
2	6		5		4		3		2		1		
3													
4	7		6		9		10		11		12		
5													
6	10		17		16		15		14		13		
7													
8	19		20		21		22		23		24		
9													
10	30		29		28		27		26		25		
11													
12	31		32		33		34		35		36		
13													

I, Stephan J. Szyszkoski, in a field survey on 07/06/15 do hereby state  
that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2  
above were in conformance with regulations and rules therefore as required in the current manual of survey  
instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of  
a Court of Law and /or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with  
the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established,  
re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded  
on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

(2-Sec. 29) East 1/16 corner between Sections 20 and 29. Not previously monumented.

(D9) Quarter corner common to Sections 20-29. 1849 - Established by John Burt, Deputy Surveyor,  
midway and on the Section line between Section corners 39.83 chains east and west. Set Maple post.  
Cedar 12" S63°E 49 links, Cedar 12" N72°W 47 links.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

(2-Sec. 29) Established the position for the corner midway and on the Section line between Section  
corner 1312.10' east and Quarter corner 1312.10' west.

(D9) The original post and accessories were not recovered. Found no evidence of the position of the  
original corner on the ground. Reestablished the position for the corner midway and on the Section  
line between Section corners 2624.19' east and west.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

(2) Set 1"IDx28" I.pipe with 2" alum. MDNR cap.  
Set measuring nail with MDNR tag in the side of:  
5" Spruce N20°W 31.7' mrkd "1/16S BT"  
5" Balsam N33°E 27.35' do  
3" Spruce N48°E 30.25' do  
Set sq'd cedar post N07°E 0.95'  
West 7' to east bank of 6' wide stream.  
E= 7907058.321 N= 166531.561

(D9) Set 1"IDx28" I.pipe with 2" alum. MDNR cap.  
Set measuring nail with MDNR tag in the side of:  
8" Tamarack N55°E 15.6' mrkd "1/4S NBT"  
6" Balsam S22°E 32.35' do  
5" Balsam S33°W 29.6' do  
7" Tamarack N64°W 45.7' do  
Set sq'd cedar post adjacent.  
E= 7906658.563 N= 166540.600

Bearings are magnetic. Coordinates are MCS83 in meters, NAD83(2011) Epoch 2010.00 datum  
Coord. Ref.=NGS PID AA8081: N= 147176.690 m. E= 7895147.466 m.

Signed by Stephan J. Szyszkoski  
Surveyor's Michigan License No. 33986

Date 08/04/2015

For the Michigan Department of Natural Resources, Forest Resources Division

