

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970 as Amended

For corners in

Iron (County) Located In: Corner Code #
1. Public Land Survey T 45N R 31W F11
T (GCDB 340200)
T 45N R 31W E11
(GCDB 300200)
2. Property Controlling in Section S T R
S T R
S T R
3. Miscellaneous Property in Sec. S T R
S T R
4. Lot No. , Recorded Plat
5. Private Claims

Register of Deeds Stamp & File Number

Table with 13 rows and 13 columns (A-M). Contains numbers 1-36 in a grid pattern.

I, Stephan J. Szyszkoski, in a field survey on 06/16/15 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and /or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

(F11) Quarter corner common to Sections 28 and 33. 1849 - Established by John Burt, Deputy Surveyor, midway and on the Section line between Section corners 40.02 chains east and west. Set sugar post. Elm 12" N78°W 25 links, Cedar 12" S82°E 18 links.

(E11) Corner common to Sections 28-29-32-33. 1849 - Established by John Burt, Deputy Surveyor. Set Y.Birch post. Cedar 7" S30°E 7 links, W.Pine 22" N41°W 39 links.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

(F11) The original post and accessories were not recovered. Found no evidence of the position of the original corner on the ground. Reestablished the position for the corner midway and on the Section line between Section corners 2637.61' east and west.

(E11) The original post and accessories were not recovered. Found no evidence of the position of the original corner on the ground. Reestablished the position for the corner by double proportionate measurement to the original record between corners E7 10484.23' north (160.00 ch. R), E13 5242.14' south (80.00 ch. R), G11 5275.22' east (80.04 ch. R), and B11 7920.65' west (120.18 ch. R).

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

(F11) Set 1"IDx28" I.pipe with 2" alum. MDNR cap. Set measuring nail with MDNR tag in the side of: 6" Poplar N16°W 25.8' mrkd "1/4S NBT" 7" Balsam S40°E 4.9' do 5" Poplar S09°W 21.5' do 5" Cherry S79°W 4.7' do Set sq'd cedar post adjacent. E= 7908246.921 N= 164917.000

(E11) Set 1"IDx28" I.pipe with 2" alum. MDNR cap. Set measuring nail with MDNR tag in the side of: 7" Maple N07°E 9.7' mrkd "S28 NBT" 9" Maple N62°E 17.7' do 9" B.Spruce S41°W 31.05' "S32 NBT" 21" W.Pine S80°W 23.8' do Set sq'd cedar post adjacent. E= 7907443.151 N= 164925.060

Bearings are magnetic. Coordinates are MCS83 in meters, NAD83(2011) Epoch 2010.00 datum. Coord. Ref.=NGS PID AA8081: N= 147176.690 m. E= 7895147.466 m.

Signed by [Signature] Surveyor's Michigan License No. 33986

Date 08/04/2015

For the Michigan Department of Natural Resources, Forest Resources Division

