

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970 as Amended

For corners in

Iron (County)	Located In:	Corner Code #
1. Public Land Survey	T 45N R 31W	M2
	T R	(GCDB 700640)
	T R	
2. Property Controlling in Section	S T R	
	S T R	
	S T R	
3. Miscellaneous Property in Sec.	S T R	
	S T R	
	S T R	
4. Lot No. , Recorded Plat		
5. Private Claims		

Register of Deeds Stamp & File Number

	A	B	C	D	E	F	G	H	I	J	K	L	M
1													
2	6		5		4		3		2		1		
3													
4	7		6		5		4		3		2		1
5													
6	10		9		8		7		6		5		4
7													
8	11		10		9		8		7		6		5
9													
10	12		11		10		9		8		7		6
11													
12	13		12		11		10		9		8		7
13													

I, Stephan J. Szyszkoski, in a field survey on 05/11/16 do hereby state
that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2
above were in conformance with regulations and rules therefore as required in the current manual of survey
instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of
a Court of Law and /or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with
the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established,
re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded
on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

Quarter corner common to Section 1 T45N-R31W and Section 6 T45N-R30W. 1969 - Reestablished by
A.O.Enger RLS by proportionate measurement on line between Section corner 120.105 chains south and
Township corner 41.888 chains north. Set 1"IDx36" I.pipe with 4" alum. cap. B.Spruce 6" S21°E 41
links, Tamarack 14" N76°E 74 links.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

Found the 1969 monument in good condition and at record bearing and distance from the remaining 1969
NBT Tamarack N76°E 74 links, alive but blazes rotted out. I note that the proportion used by Mr.
Enger is not correct. Using the GLO record 120.00 chains south and 41.65 ch. north, the proportion
should have been 120.255 ch. south (measured) and 41.738 ch. north (measured). An examination of
the 1969 calculation sheet reveals that the error is the result of Mr. Enger wrongly using the value
of 81.85 chains for the GLO record east line of Sec. 1, rather than the proper 81.65 ch. The
monument, having been in place for 47 years, is accepted as a faithful reestablishment of the
position of the original corner.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

Found 1"ID Iron pipe with 4" alum. MDNR cap.
Set measuring nail with MDNR tag in the side of:
17" Tamarack N72°E 49.65' rotted blazes (1969 NBT)
5" Poplar S47°E 12.25' mrkd "1/4S NBT"
5" Poplar S34°W 10.8' do
6" Poplar N21°W 6.55' do
Set sq'd cedar post adjacent.
E= 7913998.85 N= 172026.26

Bearings are magnetic. Coordinates are MCS83 in meters, NAD83(2011) Epoch 2010.00 datum
Coord. Ref.=NGS PID AA8080: N= 192972.689 m. E= 7925456.741 m.

Signed by Stephan J. Szyszkoski
Surveyor's Michigan License No. 33986

Date 05/19/2016

For the Michigan Department of Natural Resources, Forest Resources Division

