

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970 as Amended

For corners in

Iron (County)	Located In:	Corner Code #
1. Public Land Survey	T 45NR 31W	I7
	T R	
	T R	
	S T R	
2. Property Controlling in Section	S 23 T 45NR 31W	1
	S T R	
3. Miscellaneous Property in Sec.	S T R	
	S T R	

4. Lot No. _____, Recorded Plat _____
5. Private Claims _____

Register of Deeds Stamp & File
Number

	A	B	C	D	E	F	G	H	I	J	K	L	M
1													
2	6		5		4		3		2		1		
3													
4	7		8		9		10		11		12		
5													
6	18		17		16		15		14		13		
7													
8	19		20		21		22		23		24		
9													
10	30		29		28		27		26		25		
11													
12	31		32		33		34		35		36		
13													

Apr 12 2006

I, Stephan J. Szyszkoski, in a field survey on _____, 20____ do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and /or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

(I7) Corner common to Sections 14-15-22-23. 1970 - Remonumented by A.O.Enger RLS at an old fence intersection. Set 1"IDx36" iron pipe with 4" aluminum cap. W.Spruce 6 N15 1/2W 75.3', B.Spruce 5 N22 1/2E 88.0'.
(1-Sec. 23) West 1/16 corner between Sections 14 and 23. 1980 - Established midway between Section and Quarter corner by K.L.Sackett RLS. Mr. Sackett set 1"IDx30" I.pipe with 4" aluminum cap and made witnesses: 4" Aspen N80W 51.0', 3" Aspen S68E 8.0'.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

(I7) Recovered the 1970 monument in good condition, firmly set, at record bearing and distance from the remaining NBT B.Spruce northeast, in good condition. Left the monument in place and made new witnesses as described below.
(1-Sec. 23) Recovered the 1980 monument, cap fractured but otherwise in good condition and at record bearing and distance from the 1980 BT S68E Poplar, now dead. The other BT was not recovered. My measure shows that this monument is located 0.16' from the midpoint position of record and I accept same as a careful and faithful establishment of the position of the corner.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

(I7) Fd. 1"ID I.pipe with 4" alum. MI
Dept. of Conservation cap. Set
measuring nails in:
8" B.Spruce N27E 88.3' old blazes *
7" B.Spruce S62E 30.7' mrd "S23 NBT"
5" B.Spruce S23E 25.7' do
13" R.Pine S25W 44.7' "S22 NBT"
Set sq'd 3" B.Spruce post N73W 3.5'.
Bearings are magnetic. Distances are to
nail with tag. * denotes 1970 NBT.

(1) Fd. 1"ID I.pipe with 4" alum. MDNR
cap, fractured. Set measuring nails in:
7" Poplar N33E 43.4' mrd "1/16S BT"
6" Spruce S18E 54.0' do
7" Spruce S49W 57.1' do
5" Spruce S82W 56.0' do
Existing cedar post adjacent. Bearings
are magnetic. Distances are to nail
with tag.



Signed by

Stephan J. Szyszkoski

Date

8/1/06

Surveyor's Michigan License No.

33986

For the Michigan Department of Natural Resources, Office of Land and Facilities