

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970 as Amended

For corners in

Iron (County)	Located In:	Corner Code #
1. Public Land Survey	T _____ R _____	_____
	T _____ R _____	_____
	T _____ R _____	_____
2. Property Controlling in Section	S 16 T 45N R 34W	14
	S 21 T 45N R 34W	5
	S _____ T _____ R _____	_____
3. Miscellaneous Property in Sec.	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____
4. Lot No. _____, Recorded Plat		
5. Private Claims		

Register of Deeds Stamp & File Number

1	A	B	C	D	E	F	G	H	I	J	K	L	M
2		6		5		4		3		2		1	
3													
4		7		8		9		10		11		12	
5													
6		18		17		16		15		14		13	
7													
8		19		20		21		22		23		24	
9													
10		30		29		28		27		26		25	
11													
12		31		32		33		34		35		36	
13													

I, Stephan J. Szyszkoski, in a field survey on 5 12/20/12 do hereby state
that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2
above were in conformance with regulations and rules therefore as required in the current manual of survey
instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of
a Court of Law and /or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with
the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established,
re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded
on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

(14) South 1/16 corner between Sections 15 and 16. 1974 - Established by A.O. Enger RLS on line
between Sec. Cor 19.974 ch. South and 1/4 cor. 19.974 ch. North. Set 1"IDx36" iron pipe with 3.5"
alum. cap. Cedar 10" N4E 36.3', W. Birch 6" S87E 22.9'.

(5) North 1/16 corner, Section 21. Not previously monumented.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

(14) Found the 1974 monument in good condition, at record bearing and distance from the remains of
the 1974 witnesses (both dead with stumps in place), and in accord with the record position between
adjacent government corners. Accepted the monument as a careful and faithful determination of the
position of the corner.

(5) Established the position for the corner midway and on a straight line between Center of Section
21 1314.37' south and the 1/4 corner F7 position (in river) 1314.37' north.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

(14) Found 1"ID I. pipe with alum. State of MI cap.
Set measuring nail with MDNR tag in the side of:
3" Balsam S51E 31.9' mrkd "1/16S BT"
14" W. Spruce S34W 65.5' do
6" W. Spruce S12E 33.5' do
2" B. Spruce S01W 30.7' " X X "
Set sq'd Cedar post adjacent.
N=169069.127 E=7880245.916

(5) Set 1"IDx32" I. pipe with 4" alum. MDNR cap.
Set measuring nail with MDNR tag in the side of:
11" Spruce N34E 41.0' mrkd "1/16S BT"
3" Ash S21W 27.2' do
4" Maple S73W 18.5' do
4" Ash N38W 22.9' do
Set sq'd Cedar post adjacent.
N=168270.813 E=7879426.687

Bearings are magnetic. Coordinates are MCS83, in meters

Signed by Stephan J. Szyszkoski
Surveyor's Michigan License No. 33986

Date 01/14/2013

For the Michigan Department of Natural Resources, Forest Resources Division

