

JACKSON COUNTY
APPROVED LAND CORNER

P.A. 345 of 1990

SE CORNER SECTION #1 TOMPKINS TOWNSHIP

Chairman

Date

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

#2046611
Liber 1550 Page 927
Page 1 of 1
Jackson Co., MI
Recorded
09/10/97 12:49P
Kinky Reilly
Register of Deeds

For corners in
JACKSON

(County)

Located In:

Corner Code #

1. Public Land Survey T 1S 2W M-3
T R
T R
T R
T R
2. Property Controlling S T R
in Section S T R
3. Miscellaneous S T R
Property in Sec. S T R

SECTION

Register of Deeds Stamp & File Number

4. Lot No. , Recorded Plat
5. Private Claims

	A	B	C	D	E	F	G	H	I	J	K	L	M
2	6	5	4	3	2	1							
3													
4	7	8	9	10	11	12							
5													
6	18	17	16	15	14	13							
7													
8	19	20	21	22	23	24							
9													
10	30	29	28	27	26	25							
11													
12	31	32	33	34	35	36							
13													

RONALD L. ENGER

DECEMBER 22

92

I, , in a field survey on , 19 ,
do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned
in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the
current manual of survey instructions of the United States Department of the Interior, Bureau of Land
Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5
above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a
Court of Law; established, re-established, monumented, re-monumented, recovered, found as
expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded
on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

POST SET IN ORIGINAL GOVERNMENT SURVEY BY JOSEPH WAMPLER, DEPUTY SURVEYOR IN
JANUARY 1823 OR 1824 AND 2 BEARING TREES RECORDED: W.O. 17 N 1/2 W 53 (35.0') AND BEECH
11 S 88 W 17 (11.2'). HERVEY PARKE, D.S., SUBDIVISION OF T1S R1W, SET NEARBY CLOSING
CORNER ON MARCH 20, 1825 AND NOTED "INTERSECTED R. LINE 93 (61.4') N. OF CORNER" ON
NOVEMBER 20, 1885, JOHN HOLCROFT REPORTED "FOUND POST AT CORNER AND BOTH WITNESS
STUMPS" AND RECORDED 2 WITNESSES: BK. WALNUT 14 S75W 390 (257.4') AND BK. WALNUT 12
N66W 284-1/2 (187.8'). FIRECLAY POST FOUND DURING SURVEY FOR SUPERCONDUCTING SUPER
COLLIDER IN 1988.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

FOUND FIRECLAY POST WITH BROKEN TOP AND PINCHED PIPE AT WEST SIDE AND STEEL FENCE
POST 0.7' WEST. FOUND NO EVIDENCE OF GLO OR HOLCROFT BEARING TREES. ACCEPTED
FIRECLAY POST AS MARKER SET BY HOLCROFT AT CORNER POINT. MADE TEMPORARY
WITNESSES TO CENTER OF FC POST AND EXCAVATED TO MAKE WAY FOR NEW MARKER.
REMOVED A 14" PIECE OF FC POST, 2 OTHER PIECES OF FC POST, THE PINCHED PIPE (18"
LONG) AND MANY ROCKS. SET CONCRETE MONUMENT WITH ALUMINUM CAP AT THE CORNER
POINT. PUT MOST OF THE ROCKS IN THE HOLE AROUND THE MONUMENT. PLACED THE 14"
PIECE OF THE FC POST AT NORTH SIDE OF THE MONUMENT, TOP ABOUT 1' BELOW GRADE.


APP. ACT 345 PEER REVIEW GROUP, DEAN GUTEKUNST, CO. SURVEYOR

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

M-3, T1S R2W

4" DIAMETER X 34" CONCRETE MONUMENT WITH 1/2" X 36" REBAR AND
JACKSON COUNTY STANDARD CAP (HAS MAGNET) STAMPED LS 28409

005° NAZ, 28" WALNUT, 36.71', 40D SPIKE IN WEST SIDE
010° NAZ, FIRECLAY POST, RIVES CORNER A-3, 60.3'
025° NAZ, 8" CHERRY, 61.37', 40D SPIKE IN EAST SIDE
077° NAZ, 4" ELM, 27.52', 40D SPIKE IN SOUTH SIDE
182° NAZ, 6" ELM, 8.70', 40D SPIKE IN EAST SIDE
277° NAZ, 34" OAK, 24.45', 40D SPIKE IN SOUTH SIDE
090° NAZ, STEEL FENCE POST, 1'



Signed by

Ronald L. Enger

Date DECEMBER 30, 1992

Surveyor's Michigan License No.

28409