

LAND CORNER RECORDATION CERTIFICATE  
Filing Requirement of Act 74, Mich. P.A. 1970

For corners in

Kalkaska Located In: Corner Code #  
(County)

1. Public Land Survey T 25N R 6W D-1  
T 26N R 6W D-13

2. Property Controlling S T R  
in Section S T R  
3. Miscellaneous S T R  
Property in Sec. S T R

4. Lot No. \_\_\_\_\_, Recorded Plat \_\_\_\_\_

5. Private Claims \_\_\_\_\_

I, Craig W. McVean, in a field survey on Nov. 4 19 97 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and /or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

D-1 & D-13 - GLO - Set 1/4 Post - 1839 - H. Bervoort Jr., J.H. Mullett  
Maple 20" N31°E 28 L.  
Birch 16" N23°W 33 L.  
- W.S. Merrill - 1911 - Retrace Twp. Line.  
- Fargo Eng. - 1912 - Accept Iron corner by Co. Surveyor.  
No U.S. Evidence  
No BT's taken  
- Richards, Findorff & Richards #6764-704 - 1968 - Concrete Monument set.  
- Consumers P.C. - D.A. Ankrom - 1979 - Fnd. Conc. Mon., no witnesses.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

D-1 & D-13 - Standard 1/4 corner common to Sec. 5, T25N, R6W & Sec. 32, T26N, R6W- Fnd. Concrete Mon. w/ 1/2" iron on S.side of wood anchor post at intersection of fence remains N,S,E.& W. Dug around Mon. & fence corner but no Fargo Pipe or crockery was found. Accepted Conc. Mon. as the best available evidence of the position of the original corner.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

D-1 & D-13 - Fnd. Conc. Mon. w/ 1/2" iron  
S7°E 38.25' to N&T in E. side 6" B. Cherry  
N69°E 27.59' to N&T in S. side 6" B. Cherry  
N40°E 64.09' to N&T in SE. side 7" W. Pine  
N54°W 167.95' to N&T in SW. side 4" W. Pine  
Set Blue Carsonite Post 1' SE

SURVEY &  
REGISTERED  
JAN 11 2000  
SECTION

Register of Deeds Stamp & File Number

	A	B	C	D	E	F	G	H	I	J	K	L	M
1													
2	6		5		4		3		2		1		
3													
4	7		8		9		10		11		12		
5													
6	18		17		16		15		14		13		
7													
8	19		20		21		22		23		24		
9													
10	30		29		28		27		26		25		
11													
12	31		32		33		34		35		36		
13													

Signed by Craig W. McVean  
Surveyor's Michigan License No. 39088


Date 12/9/1999



Ratified by Peer Group  
P.A. 345 - 1990 Kalkaska County  
Chairman [Signature]  
Date 9-14-99

FORM APPROVED BY MICHIGAN STATE BOARD OF PROFESSIONAL SURVEYORS, JAN. 28, 1971  
REVISED MAY 14, 1975

REVISED JAN., 1983  
REVISED OCT., 1995



3019500  
Page: 1 of 1  
12/23/1999 11:02A  
REMON  
LB: 6 PG: 56