



8 0 2 3 2 7 0

Tx:4016447

11/29/2012 1:00:00 PM

LAND CORNER RECORDATION CERTIFICATE

Filing Requirement of Act 74, Mich. PA 1970

For Corners In:

Kalkaska

(County)

Located In

Corner Code #

| | | | | | |
|--------------------------------------|---|-----|---|----|----|
| 1. Public Land Survey | T | 26N | R | 6W | E8 |
| | T | | R | | |
| 2. Property Controlling in Section | S | T | R | | |
| | S | T | R | | |
| 3. Miscellaneous Property in Section | S | T | R | | |
| | S | T | R | | |

4. Lot No: _____ Recorded Plat: _____

5. Private Claims: _____

I, Joshua R. Davidson, in a field survey on December 6, 2012 do hereby state that under requirements of PA 74, Michigan PA of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

DOCUMENT #

3111412

JOANN DEGRAAF

KALKASKA CTY ROD

KALKASKA, MI

RECORDED ON


11/29/2012 1:31 PM

REC FEE: 14.00

PAGES: 1

BK: 3PG: 336

Register of Deeds Stamp & File Number



A. Description of original monument and accessories and/or subsequent restoration:

E8 – 1852 – GLO, G. Cannon – Set ¼ sec. post

1) Tamarack 16" S50°E 25

2) W. Pine 12" S80°W 26

1901 – County Surveyor, Merrill – FB 20, p. 67, shows corner1959 – DNR corner record, K. J. Ostling, PS#10068. Found the government post from both BT's. The SW W. Pine in place with good marks and the SE Tamarack in place with evidence of face. Checks swamp edge & line tree north.

Set 1" Pipe with 4" Brass Cap.

3) 7" Cedar S35°W 32 ½ L.

4) 10" Cedar S69°E 22 ½ L.

B. Description of corner evidence found and/or method applied in restoring or re-establishing corner:

E8 – ¼ corner common to sections 20 & 21, T26N, R6W. Found 4" Department of Conservation (DOC) brass cap on 1" galvanized iron pipe and witnesses #3 & #4 fitting position per the 1959 Ostling corner record. Found stump remains of both GLO Bearing trees, fitting position. Marks still visible on White Pine stump. Witness #3 in good shape, witness #4 is dead but still standing. DOC brass monument accepted as a careful and faithful perpetuation of the position of the original corner.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

E8 – Found 4" stamped DOC brass cap on 1" galvanized iron pipe

N47°E 13.22' to set nail & tag in NW. side 7" Cedar

S65°E 14.5' to notch on face of 12" dead standing Cedar (#4)

S30°E 9.79' to set nail & tag in NE. side 10" Cedar

S40°W 21.70' to set nail & tag in SE. side 10" Cedar (#3)

N62°W 36.13' to set nail & tag in N. side 8" Cedar scribed "XBT"

Set blue Carsonite post 1' Northeast



Signed by:

Joshua R. Davidson

Date:

11-29-2012

Surveyor's Michigan License No.:

46659