

**SURVEY &
REMONUMENTATION**

MAR 21 1997

COMMISSION

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

KALKASKA COUNTY, MICHIGAN
RECEIVED
97 JAN 31 PM 3:19

For corners in

KALKASKA

(County)

Located In:

Corner Code ##

1996 REMONUMENTATION

1. Public Land Survey

T 26N R 7W

C-2

T _____ R _____

T _____ R _____

T _____ R _____

2. Property Controlling
in Section

S _____ T _____ R _____

3. Miscellaneous

S _____ T _____ R _____

Property in Sec.

S _____ T _____ R _____

4. Lot No. _____, Recorded Plat _____

5. Private Claims _____

Register of Deeds Stamp & File Number

I, EUGENE FARRIER, in a field survey on July 1, 19 96,
do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned
in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the
current manual of survey instructions of the United States Department of the Interior, Bureau of Land
Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5
above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a
Court of Law; established, re-established, monumented, re-monumented, recovered, found as
expressed below:

**NOTE: Not more than 4 corners, all in the same town and range, may be recorded
on this certificate.**

A. Description of original monument and accessories and/or subsequent restoration:

C-02: Cor. common to Sec. 5 & 6, T26N-R7W, Orange Township
1849, GLO resurvey, set Hemlock post. 6" Beech N33W 21, 6" Hemlock N28E 14.
Apr 13-1905, W.S. Merrill, Co. Surveyor, used corner, 40" Pine Stump N37E
25, 30" Pine Stump S55W 13.
May 12, 1987, C.F. Roser, fd. 1" iron, accessories are same as 1905.
May 12, 1987, LCRC Liber 2 pg. 348.
03-05-1990, E.D. Farrier, Survey #2886B, fd. 1" iron w/ accessories.
07-31-1991, E.D. Farrier, Survey #6991, fd. 1" iron w/ accessories.
10-10-1994, E.D. Farrier, Survey #26894, fd 1" iron w/ accessories.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

C-02: Cor. common to Sec. 5 & 6, T26N-R7W, Orange Township
Found 1" x 24" iron pipe w/ accessories. Pulled & Set 5/8" x 18" re-rod w/
Brass cap 0.5' below two track, cor falls centerline of two track in line
with old fence to the West. No G.L.O. witnesses were found. The Kalkaska
Co. peer group approved & accepted the above monument as a careful and
faithful perpetuation of the position of the original corner.


Ratified by Peer Group
P.A. 345 - 1990 Kalkaska County

Chairman Eugene Farrier

Date 1-21-97

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

C-02: Cor. common to Sec. 5 & 6, T26N-R7W, Orange Township
Found 1" x 24" iron pipe w/ accessories. Pulled & Set 5/8" x 18" re-rod w/
Brass cap 0.5' below two track, cor falls centerline of two track in line
with old fence to the West.
Set nail & tag S49W, 6" Tri Maple, 27.59
S87W, Face DNR Post, 16.17'
Set nail & tag N30W, 10" Twin Cherry, 21.48'
Set nail & tag S42E, 7" Poplar, 19.02



Signed by Eugene Farrier

Date 1-30-97

Surveyor's Michigan License No. 24594