

# SURVEY & REMONUMENTATION

JAN 17 1996

COMMISSION

LAND CORNER RECORDATION CERTIFICATE  
Filing Requirement of Act 74, Mich. P.A. 1970

For corners in

KALKASKA

(County)

Located In:

Corner Code #1

1995 REMONUMENTATION

- |                                    |       |      |     |
|------------------------------------|-------|------|-----|
| 1. Public Land Survey              | T 26N | R 7W | G-2 |
|                                    | T     | R    |     |
|                                    | T     | R    |     |
|                                    | T     | R    |     |
| 2. Property Controlling in Section | S     | T    | R   |
|                                    | S     | T    | R   |
| 3. Miscellaneous                   | S     | T    | R   |
| Property in Sec.                   | S     | T    | R   |

Register of Deeds Stamp & File Number

4. Lot No. \_\_\_\_\_, Recorded Plat \_\_\_\_\_  
5. Private Claims \_\_\_\_\_

I, EUGENE FARRIER, in a field survey on Oct. 23, 19 95, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

G-2: 1/4 Cor. common to Sec. 3 & 4, T26N-R7W, Orange  
1849 GLO re-survey: set Bech 1/4 post, Sgr 12", S65W, 33; Sgr 14", N64E, 20.  
4-27-1897, E.P. Beebe, Surv., Hwy. Surv. used crnr, no accessories.  
1-3-1983, E.D. Farrier, CERT OF SURVEY, set 1/2" iron w/cap #33969.  
6-3-1993, E.D. Farrier, CERT OF SURV, fd. 1/2" iron w/cap #33969, L.1 PG. 759.  
6-6-1993, LCRC (E.D. Farrier), set 1/2" iron w/cap.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

G-2: 1/4 Cor. common to Sec. 3 & 4, T26N-R7W, Orange  
Fd 1/2" iron w/cap #33969, 2.5' West c/l Mitchell Road and 1' North of E-W fence. Pulled & replaced with 5/8" x 18" R.B. w/brass cap 0.3' below Rd. Surface. No GLO wit. were fd. The Kalkaska Co. peer group approved the above monument as a careful and faithful reestablishment of the position of the original corner.

Ratified by Peer Group  
P.A. 345 - 1990 Kalkaska County

Chairman Eugene Farrier

Date 12-19-95


C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

G-2: 1/4 Cor. common to Sec. 3 & 4, T26N-R7W, Orange  
Fd 1/2" iron w/cap #33969. Pulled & replaced with 5/8" x 18" R.B. w/brass cap 0.3' below Rd. Surface.  
Set nail & tag S39W, 9" R. Pine, 66.63'  
Set nail & tag S77W, 6" R. Pine, 53.63'  
Set nail & tag West, P.P., 30.67'  
Set nail & tag S36E, 14" Maple, 52.91'

Signed by Eugene Farrier

Date 12-22-95

Surveyor's Michigan License No. 24594



FORM APPROVED BY MICHIGAN STATE BOARD OF SURVEYORS JAN 28, 1995  
REVISED JAN. 15