

SURVEY & REMONUMENTATION

JAN 17 1996

LAND CORNER RECORDATION CERTIFICATE Filing Requirement of Act 74, Mich. P.A. 1970

KALKASKA COUNTY, MICHIGAN
RECEIVED

95 DEC 27 AM 9:53

For corners in

COMMISSION

KALKASKA
(County)

Located In:

Corner Code ##

1995 REMONUMENTATION

- | | | |
|-------------------------|------------|------|
| 1. Public Land Survey | T 27N R 7W | F-13 |
| | T R | |
| | T R | |
| | T R | |
| 2. Property Controlling | S T R | |
| in Section | S T R | |
| 3. Miscellaneous | S T R | |
| Property in Sec. | S T R | |

Register of Deeds Stamp & File Number

4. Lot No. _____, Recorded Plat _____
5. Private Claims _____

I, EUGENE FARRIER, in a field survey on Oct. 18, 19 95, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

F-13: S 1/4 Cor. of Sec. 33, T27N-R7W, Kalkaska
1850 GLO re-survey: set 1/4 sec. post, Bech 7", S2W, 27; Bech 10", N10E, 26.
1901, W.S. Merrill, Co. Surveyor, fd. stone corner.
9-22-1975, H.L. Fluharty, CERT OF SURV, ties crnr, ran S. line Sec. 33, indicates crnr midway & on line, L.1 PG. 759.
11-5-1975, LCRC (H.L. Fluharty), F-13, fd 1 3/4" iron hub, L.1 PG. 365-A.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

F-13: S 1/4 Cor. of Sec. 33, T27N-R7W, Kalkaska
Fd 5/8" x 18" R.B. w/cap #18223, 2' South of Anderson Rd. & 57' East of c/l of Krumlauf Rd. Pulled & replaced with 5/8" x 18" R.B. w/brass cap 0.3' below Rd. Surface. No GLO wit. were fd. The Kalkaska Co. peer group approved the above monument as a careful and faithful reestablishment of the position of the original corner.

Ratified by Peer Group
P.A. 345 - 1990 Kalkaska County
Chairman Eugene Farrier
Date 12-19-95


C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

F-13: S 1/4 Cor. of Sec. 33, T27N-R7W, Kalkaska
Fd 5/8" x 18" R.B. w/cap #18223. Pulled & replace with 5/8" x 18" R.B. w/brass cap 0.3' below Rd. Surface.
Set nail & tag N10E, SE cor of shed, 105.48'
Set nail & tag N40E, SW cor of house, 129.26'
Set nail & tag N82E, P.P., 164.56'
West, N 1/4 Cor, Sec. 4, T26N-R7W, Kal. Co. Mon., 57.10'

Signed by Eugene Farrier

Date 12-22-95

Surveyor's Michigan License No. 24594



FORM APPROVED BY MICHIGAN STATE BOARD OF SURVEYORS
REVISED JAN. 1